



MAHA TRANSCO

MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO.LTD.

(CIN No. U40109MH2005SGC153646)

From:- Executive Engineer (Civil)

EHV Civil Construction cum Maintenances Division Nashik

"Administrative Building", Block No. 6, 1st floor, Racca Plot,

Old Saikheda Road, Jail Road, Nashik Road-422 101.

Ph No.:-0253-2403101 (O), Extension Phone No, 0253-2403110

E-Mail ID : ee5710@mahatransco.in Website: www.mahatransco.in

Ref. No. EEC/EHV/CCCM Dn/NSK/Tech- **No - 148** - Date:- **10 FEB 2022**

e- Quotation

Sealed and superscripted e- quotations are invited for the work of **"Miscellaneous & Electrification work control room at 132 KV Khaprale Sub station, Tal:- Sinnar, Dist:- Nashik."** As detailed in schedule "B" is enclosed herewith subject to following terms and conditions.

Name of Work:- Miscellaneous & Electrification work control room at 132 KV Khaprale Sub station,
Tal:- Sinnar, Dist:- Nashik.

The quotations should reach to this office on or before **16/02/2022** up to 15.00 Hrs

- 1) The rates [percentage] should be quoted on Firm Quotation basis (Two Bid System only) including cost of materials, labours & T&P etc. required for execution of the work.
 - (a) **Compulsory Primary Documents in 1st Envelop:(Technical Bid)**
 - (i) Valid Certificate of Electrical Contractor License and registration.
 - (ii) GST/ GSTIN Registration Certificate.
 - (iii) Experience of having successfully completed similar types of works.
 - (iv) PAN card.
 - (v) Shop Act certificate/ Udyog Adhar Registration.
 - (vi) Payment of **EMD Rs. 3000.00** to be made by bidder off-line only upto 14.00 hrs of **16/02/2022** in the office of EE(C), Dn., Nashik. EMD details Amount and M.R. No. should be super-scribed on the Envelope and having registered vendor of MSETCL.
 - (b) **Documents in 2nd Envelop:(Price Bid)**
 - i) Price bid only where in the rates/percentage should be quoted in figures as well as in words.

NOTE:- Envelop No.2 (Price Bid) will be opened after qualifying in (Technical Bid) Envelop No.1

- 2) The quantities enumerated in here attached Schedule B are approximate, however the payment will be made against actual executed quantities on site.
- 3) The work should be completed within **15 days** from the date of handing over the site to commence the work, failing of which a penalty at ½% per week subject to the maximum 10% of the ordered value will be imposed.
- 4) The work should be strictly carried out as per standard specifications & up to the entire satisfaction of the Engineer-in-charge.

- 5) No materials will be supplied by the MSETCL for this work except materials as shown in Schedule A
- 6) Payment will be made through First & Final bill/ R.A. bill basis at the discretion of undersigned.
- 7) The contractor will have to pay security deposit to this office equal to 5% of the ordered value.
- 8) In case any accident occurred to the Contractor's labour/workmen during execution of work, the contractor will be fully responsible for all claims & compensation. No charge in any case will be borne by the MSETCL
- 9) The materials to be utilized for the work should be getting approved from the Engineer-in-charge prior to its utilization for the work.
- 10) The terms & conditions enumerated in the approved Booklet "TENDER AND CONTRACTOR FOR WORKS" will be applied in this case & will be binding on the contractor entirely.
- 11) Right to accept any or to reject any or all the quotations without assigning any reason there of is reserved by the undersigned.
- 12) Payment will be released to agency as per availability of funds. Further MSETCL will not pay any compensation due to non availability of funds.

Yours faithfully,

(V. M. Dhore)
Executive Engineer [Civil]
EHV Civil CCM Dn Nashik.

Copy s.w.r.to.-

- 1) The Superintending Engineer (Civil) EHV CCCM Circle, Nashik.

Copy to-

- 1) The Dy. Manager [F&A] Dn. Office, Nashik.
- 2) Master File/Notice Board.

MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO.LTD
EHV CCCM Division, Nashik

Name of work :-Miscellaneous & Electrification work control room at 132 KV Khaprle Sub station, Tal:- Sinnar,
Dist:- Nashik

SCHEDULE 'B'

Item No	Elect.CS R 2021-22	Description	Qty	Rate	Unit	Amount
1	1-2-2	Supplying and erecting UPVC reinforced flexible conduit 25 mm in dia. conforming to I.S. with required number of couplings, PVC bushes, check nuts etc. complete	15.00	90.00	Mtr	1350.00
2	1-2-10	Supplying & laying HMS PVC trunking (PVC Casing-Capping) 25 mm dia with necessary accessories on wall/ceiling as per specification No. WG-MA/CON	55.00	38.00	Mtr	2090.00
3	1-1-9	Supplying & laying HMS PVC Conduit Pipe 25 mm dia with necessary accessories on wall/ceiling as per specification No. WG-MA/CC	100.00	112.00	Mtr	11200.00
4	1-3-2+1-3-2 40+20	Supplying & erecting mains with 2x1.5 sq.mm FRLSH copper PVC insulated wire with 1x1.5 sq.mm FRLSH Green colour earth wire laid in provided conduit/trunking/ inside pole/Bus bars or any other places as per specification No: WGMA/BW	60.00	60.00	Mtr	3600.00
5	1-3-3+1-3-3 57+28.5	Supplying & erecting mains with 2x2.5 sq.mm FRLSH copper PVC insulated wire with 1x2.5 sq.mm FRLSH Green colour earth wire laid in provided conduit/trunking/ inside pole/Bus bars or any other places as per specification No: WGMA/BW	178.00	86.00	Mtr	15308.00
6	1-3-6 + 1-3-3 83+28.5	Supplying & erecting mains with 2x4 sq.mm FRLSH copper PVC insulated wire with 1x2.5 sq.mm FRLSH Green colour earth wire laid in provided conduit/trunking/ inside pole/Bus bars or any other places. as per specification No: WGMA/BW	200.00	112.00	Mtr	22400.00
		Moduler Accessories				
7	1-7-7	Supplying and erecting Ceiling rose / Batten holder /Slanting holder / hanging cord switch / hanging bell push / pendent holder bakelite base 6A. erected on filled polypropylene board or polished double wooden block/ PVC junction box.	20.00	35.00	Each	700.00
8	1-8-6	Supplying and erecting ISI mark modular type switch 16 / 20 A with indicator, duly erected on provided plate and box with wiring connections complete	5.00	134.00	Each	670.00
9	1-8-11	Supplying and erecting ISI mark modular type 3 pin 6 / 16A multi socket with safety shutter, duly erected on provided plate and box with wiring connections complete.	5.00	166.00	Each	830.00
10	1-8-25	Supplying and erecting ISI mark modular type blanking plate two module, duly erected on provided plate & box.	15.00	24.00	Each	360.00
11	1-8-28	Supplying and erecting surface modular switch box with double mounting plate for 3 module duly erected.	2.00	151.00	Each	302.00
12	1-8-32	Supplying and erecting surface modular switch box with double mounting plate for 12 module duly erected.	5.00	330.00	Each	1650.00
13	1-8-33	Supplying and erecting surface modular switch box with double mounting plate for 16 / 18 module duly erected.	3.00	366.00	Each	1098.00

Ite m No	Elect.CS R 2021- 22	Description	Qty	Rate	Unit	Amount
14	1-8-15	Supplying and erecting ISI marked modular type telephone socket one gang with safety shutter, duly erected on provided plate and box with wiring connections complete	2.00	89.00	Each	178.00
		Point wiring				
15	1-9-26	Point wiring in PVC trunking (casing-capping) with 1.5 sq.mm (2+1E) FRLSH grade copper wire, modular type switch, earthing and required accessories as per specification No: WG-PW/SW	39.00	469.00	Point	18291.00
16	1-9-28	Point wiring for independent plug in PVC trunking (casingcapping) with 1.5 sq.mm (2+1E)FRLSH grade copper wire, modular type switch, earthing and required accessories as per specification No: WG-PW/SW	16.00	634.00	Point	10144.00
17	1-9-23	Secondary point wiring for additional light/ bell point, in min 20 mm PVC trunking (cassing-capping) with 1.5 sq.mm. (2+1E) FR/FRLSH grade copper wires with required accessories as per specification No: WG-PW/CW	10.00	172.00	Point	1720.00
		Fixtures				
18	2-1-23	Supplying & erecting LED 20W tube light fitting (4 feet) with aluminium housing, heat sink, integrated HF electronic driver complete	16.00	926.00	Each	14816.00
19	2-12-21	Supplying and erecting five star rated energy saving Ceiling fan 230 V A.C. 50 cycles 1200 mm complete erected in position as per specification no. FG-FN/CF	12.00	2042.00	Each	24504.00
20	9-1-3	Providing earthing with galvanized iron earth plate size 60 x 60 x 0.6 cm with funnel with a wire mesh for watering complete with all materials, testing & recording the results as per specification no. EA-EP	1.00	5476.00	Each	5476.00
21	2-1-11	Supplying and erecting square shaped CRCA /die-cast aluminium powder coated housing LED panel light (slim edge-lit) 600x600mm suitable for 36 W-40W with provision for plane front frame with translucent cover fixed to the housing complete.	26.00	3741.00	Each	97266.00
22	1-15-1	Dismantling the existing light, fan, bell, clock, independent plug point, wiring including circuit mains of all types along with accessories etc. complete as per specification No: WG-DM/PW	20.00	8.00	Each	160.00
23	2-1-4	Supplying and erecting LED square / circular 16 to 20 W down lighter having pressure die-cast aluminum housing, opal translucent cover, mounting arrangement with board for surface type or spring loaded mounting clips for flush type complete.	2.00	1252.00	Each	2504.00
24	1-8-1	Supplying and erecting ISI mark modular type switch 6A / 10A duly erected on provided plate and box with wiring connections complete.	25.00	70.00	Each	1750.00
25	1-8-23	Supplying and erecting ISI mark modular type (two module) electronic step regulator for fan, duly erected on provided plate and box with wiring connections complete. Note: Add Rs 57/- for additional two module box with double mounting plate if required.	12.00	368.00	Each	4416.00

Ite m No	Elect.CS R 2021- 22	Description	Qty	Rate	Unit	Amount
26	5-3-11	Supplying, erecting & marking SPN MCB 6A to 32A, Bseries (for lighting) in provided distribution board as per specification no. SW-SWR/MCB	10.00	405.00	Each	4050.00
27	5-4-4	Supplying and erecting triple pole and neutral distribution board (TPNDB) surface/ flush mounted SP/TP MCBs of 12 poles/4 ways on iron / GI frame (vertical busbar type) as per specification no. SW-SWR/MCBDB	1.00	4057.00	Each	4057.00
28	5-3-26	Supplying erecting and marking four pole isolators only switch version of miniature circuit breakers of 80/100A in provided distribution board complete.	1.00	819.00	Each	819.00
29	5-3-25	Supplying erecting and marking four pole isolators only switch version of miniature circuit breakers of 63A in provided distribution board complete.	2.00	657.00	Each	1314.00
30	5-3-20	Supplying erecting and marking double pole isolator only switch version of miniature circuit breaker of 40A with required wiring connections and lugs etc. in provided distribution board complete.	3.00	293.00	Each	879.00
31	1-8-31	Supplying and erecting surface modular switch box with double mounting plate for 8 module duly erected.	1.00	256.00	Each	256.00
Total Rs.						254158.00
Add GST 18%						45748.44
Total Rs.						299906.44
Say Rs.						299906.00


Executive Engineer (Civil)
EHV CCCM Dn Nashik.

I / We hereby agree to carryout the above work as under :-

- At estimated cost.
- Above.....% in words.....Of Estimated cost in Schedule "B"
- Below.....% in words.....Of Estimated cost in Schedule "B"

I/ We have read the instructions and the same are binding on me / us.

Signature of the Contractors & Address.