

MAHARASHTRA STATE ELECTRICITY TRANSMISSION COMPANY LTD.
EHV (O&M) DIVISION, JALGAON.
(CIN No. U40109MH2005SGC153646)

Office of the:-

Executive Engineer, EHV O&M Division
Plot No.32, M-Sector
Near Godavari Engineering College
New MIDC Jalgaon
Contact No. :- 0257-2212769(O) Fax- 2212770
Email Id :- ee5210@mahatransco.in

No. EE/ EHV/ O&M/ Dn./JLG/ Tech/No.

No 00295
E-Enquiry - 31/2021-22

Date:-

8 MAR 2022

Sub: - E-Enquiry for inviting the Quotation for the Providing & Fixing of 16/20-Windows Annunciators to alarming abnormal Condition of 11 KV GIS system & associated work at 132KV S/Stn ECR Deepnagar under EHV O&M Division, Jalgaon. ...

Dear Sir,

With ref to the above, please quote your lowest rates for the following work subject to the terms & conditions mentioned as under. The sealed subscribed Quotations with valid relevant document should reach to this office on or before 17.03.2022 up to 16.00 Hrs. The same quotations will be opened on the same date at 16.30 Hrs, if possible.

TERMS AND CONDITIONS

The quotation must be forwarded in sealed envelope duly super scribed with all details i.e.

I. Enquiry No. & Date : II. Due Date: III. Quotation for:-

- 1. Scope Of Works:** The detail scope of work mentioned in Schedule "A" at 132KV S/Stn ECR Deepnagar.
- 2. Quoted Rates:** You are requested to quote your unit rates for the items mentioned in the schedule on firm (percentage) basis. (Please quote ex-works price in ex-works field & applicable GST in GST field)
- 3. Payment:** On completion of the job, the bill (in triplicate) should be submitted to the concerned Engineer in charge. The concerned Engineer In Charge will verify and process the bill and submit to division office along with his certificate & MIGO/SES as applicable. The payment will be effected by this office within a reasonable time as per actual work done.
- 4. Documents required to be attached along with offer:-** Following are the list of qualifying documents required please attached for qualifying in the e-enquiry.
 - Full name of quotation submitting firm & full address of the same.
 - Valid GST Registration Certificate.
 - Valid Electrical Contractor licenses.
 - Valid Shop Act.
 - Work order and Work completion certificate of Similar/related type of works as a Proof of Experience.
- 5. Rates & Taxes:** - The Rates quoted should be valid at least for **02 months** and should be including of all Labour charges & incidental charges including labour cess but excluding GST as per applicable rate & relevant act. Please quote your GST registration No on quotation.
- 6. Work completion:** - The work shall be completed within **60 days** from the date of issuing final work order.
- 7. Penalty:** - If the supply as well as work is not completed within stipulated period the penalty @ $\frac{1}{2}\%$ per week subject to maximum 10% of the order value of work, will be levied. Loss to MSETCL property or equivalent etc. due to your negligence will be penalized & will be recovered from the bill.

8. **Delivery:** - You will have to arrange for transportation of materials to site/SS require for completion of work at your cost.
9. **T&P:** - All the T&P, required for above work will be arranged by the Contractor.
10. **Safety:** - The contractor shall ensure the safety of all the workmen, materials and equipment either belonging to him or to other working at site. The contractor shall be responsible for providing of all safety notices and safety equipment required. If any accident occurs during the work, the complete responsibility of the accident will be of Contractors. The M.S.E.T.Co.Ltd. shall not pay any type of compensation for any type of accident.
11. **TDS under Income tax Act and TDS under GST Act :** -TDS under Income tax Act and TDS under GST Act at source as per prevailing rate & applicable as per Govt. rules – amended from time to time will be deducted from your bill.
12. **Insurance:** It is responsibility of contractor to takeout all necessary insurance of materials/equipment/labour for execution of work for his liabilities direct/indirect and same must be attached with invoice otherwise 1% on work order value will be deducted from bill.
13. **Labour Cess:** Labour cess @1% under the Building other Construction Workers Welfare Cess Act, 1996 and rate made their under shall be deducted on total contract value.
14. **Quality:-**The agency will be fully responsible for quality of the material used and the workmanship for the subjected works.
15. **Security Deposit:** - The Bidder will have to pay security deposit within seven days from the date of receipt of the LOI, amounting to 05% of the value of the contract in the form D.D./F.D. of any Nationalized / scheduled Bank in the name of **Executive Engineer EHV O&M Division, Jalgaon, payable at Jalgaon at EHV O&M Division, Jalgaon office** or in the form of Bank Guarantee in favour of **Executive Engineer EHV O&M Division, Jalgaon** valid for one year at this office. The same will be refunded only after satisfactory completion of guarantee period.
16. **Accommodation:-** No living accommodation at site will be provided by M.S.E.T.C.L.
17. **Agreement:-** You will have to execute agreement as per provision of Mumbai MudrankAdhiniyam 1958, Clause No.34 with requisite stamp duty (Rs. 500/-) before issuing of final work order.
18. **General:** - MSETCL general Terms and Conditions for works are applicable to this contract. The undersigned reserves the rights to accept or reject any or all the Quotation without assigning any reason thereof.
19. **Guarantee:** - All the material supplied and the workmanship shall be guaranteed for the 01 year from the actual completion of the subjected work for trouble free service.
20. **Particulars of work (Detail description of Service / Materials, unit) given in schedule of this legacy enquiry is final.** For any Dispute arise decision of the under signed will be final.
21. The undersigned have the reserve right for relaxation of any condition mention above & also reserves the rights for cancellation of any or all quotations/enquiry without assigning any reason.
22. Acceptance of work order shall be treated as acceptance of these conditions of the e-enquiry by contractor.

Thanking you,

Yours Faithfully,



(Vinod R Lokhande)

Executive Engineer

EHV (O&M) Division, Jalgaon.

Copy s.w.r. to: -

The Superintending Engineer, EHV O&M Circle, Bhusawal. (By email)

Copy to:-

1. The Dy. Manager [F&A], EHV O&M Division, Jalgaon. (By email)


2. The Web Master, MSETCL.(By email)

3. Notice Board.

MAHARASHTRA STATE ELECTRICITY TRANSMISSION COMPANY LTD.**EHV (O&M) DIVISION, JALGAON.****(CIN No. U40102MH2005SGC153646)****"Schedule A"**

Sub: - Providing & fixing of 16/20-Window Annunciators to alarming abnormal Condition of 11 KV GIS system & associated work at 132KV S/Sm ECR Deepnagar under EHV O&M Division, Jalgaon. ...

Sr. No.	Description	Unit	Qty.	Unit Rate	Unit Rate Including GST	Remark
1	Supply Micro controller 20 Window Annunciator	EA	3			
2	Installation & comm. Window annunciator -20 Window	EA	3			
3	Supply Micro controller 16 Window Annunciator	EA	8			
4	Installation & comm. Window annunciator -16 Window	EA	8			
5	Cable termination for 12 C X 2.5 sqmm at both ends as per termination schedule provided with cable glanding at both ends panels/ MB etc. with drilling of suitable size holes for cable glands as per cable sizes with spare holes as directed, glanding the cable with proper size glands to make it tight and firm, checking the cables cores from both side for continuity with suitable arrangement and providing the cross ferruling as per cable schedule to both ends of cable and crimping of suitable size required lugs as per cable core size with suitable crimping tool making it tight connection and then dressing up the same in TB's provided in Panels / MB etc. as directed for the following cables with sealing of spare holes... BY PROVIDING REQD SIZE LUGS , GLANDS AND FERRULES	Per cable	18			
6	Supply of Cable trays 200 X 20 mm, perforated GI	RMT	70			
7	Fixing of provided 200 X 20 mm cable trays on the M.S. Angles with suitable size nut bolts with necessary cutting/ fabrication / bending etc. complete as directed with flushing with curlier trays 90 deg turn wherever required ... BY PROVIDING NUT BOLTS AS REQD	RMT	70			
8	Supply of 3.5C x 70sq mm Aluminium, Armoured power cable (1100 V LT)	KM	0.13			
9	Laying of 1100 V LT Power cable (3.5 X 70 sq.mm)	RMT	130			
10	Termination of 1100 V LT Power cable at both ends (Inclusive of glands, lugs, ferrules etc.)	Per cable	1			
11	AC auxiliary DB (Outdoor)	Each	1			
12	Modification of Panel for mounting of 16 Window Annunciator	LS	2			


(Vinod R Lokhande)
Executive Engineer
EHV (O&M) Division, Jalgaon.