



## MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO.LTD.

(CIN No. U40109MH2005SGC153646)

From:- Executive Engineer (Civil)  
EHV Civil Construction cum Maintenances Division Nashik  
"Administrative Building", Block No. 6, 1<sup>st</sup> floor, Racca Plot,  
Old Saikheda Road, Jail Road, Nashik Road-422 101.  
Ph No.:-0253-2403101 (O), Extension Phone No, 0253-2403110  
E-Mail ID :ee5710@mahatransco.in Website: www.mahatransco.in

Ref. No. EEC/EHV/CCCM Dn/NSK/Tech- **No - 3 3 3** - Date:- **22 MAR 2022**

### e- Quotation

Sealed and superscripted e- quotations are invited for the work of "Various civil maintenance work in 33 KV yard and colony at 132 KV Rahuri Sub station, Tal:- Rahuri, Dist:- Ahmednagar." As detailed in schedule "B" is enclosed herewith subject to following terms and conditions.

**Name of Work:-** Various civil maintenance work in 33 KV yard and colony at 132 KV Rahuri Sub station, Tal:- Rahuri, Dist:- Ahmednagar.

The quotations should reach to this office on or before **29/03/2021** up to 15.00 Hrs

- 1) The rates [percentage] should be quoted on Firm Quotation basis (Two Bid System only) including cost of materials, labours & T&P etc. required for execution of the work.

**(a) Compulsory Primary Documents in 1<sup>st</sup> Envelop:(Technical Bid)**

- (i) Valid Certificate of Registration of appropriate class for Civil works from PWD /MES/ Railways/ Jeevan Pradhikaran ETC.OR From Any Govt. / Central Government and registered vendor of MSETCL.
- (ii) GST/ GSTIN Registration Certificate.
- (iii) PAN Card
- (iv) E.P.F. Registration Certificate – issued by competent authority of Govt.
- (v) Experience of having successfully completed similar civil works.
- (vi) Payment of **EMD Rs. 9990.00** to be made by bidder off-line in cash only upto 14.00 hrs of **29/03/2022** in the office of EE(C), Dn., Nashik. EMD details Amount and M.R. No. should be super-scribed on the Envelope & having registered vendor of MSETCL.

**(b) Documents in 2<sup>nd</sup> Envelop:(Price Bid)**

- i) Price bid only where in the rates/percentage should be quoted in figures as well as in words.

**NOTE:- Envelop No.2 (Price Bid) will be opened after qualifying in (Technical Bid) Envelop No.1**

- 2) The quantities enumerated in here attached Schedule B are approximate, however the payment will be made against actual executed quantities on site.



- 3) The work should be completed within **15 days** from the date of handing over the site to commence the work, failing of which a penalty at  $\frac{1}{2}\%$  per week subject to the maximum 10% of the ordered value will be imposed.
- 4) The work should be strictly carried out as per standard specifications & up to the entire satisfaction of the Engineer-in-charge.
- 5) No materials will be supplied by the MSETCL for this work except materials as shown in Schedule A
- 6) Payment will be made through First & Final bill/ R.A. bill basis at the discretion of undersigned.
- 7) The contractor will have to pay security deposit to this office equal to 5% of the ordered value.
- 8) In case any accident occurred to the Contractor's labour/workmen during execution of work, the contractor will be fully responsible for all claims & compensation. No charge in any case will be borne by the MSETCL
- 9) The materials to be utilized for the work should be getting approved from the Engineer-in-charge prior to its utilization for the work.
- 10) The terms & conditions enumerated in the approved Booklet "TENDER AND CONTRACTOR FOR WORKS" will be applied in this case & will be binding on the contractor entirely.
- 11) Right to accept any or to reject any or all the quotations without assigning any reason there of is reserved by the undersigned.
- 12) Payment will be released to agency as per availability of funds. Further MSETCL will not pay any compensation due to non availability of funds.

**Yours faithfully,**



**(V. M. Dhore)**  
**Executive Engineer (Civil)**  
**EHV Civil CCM Dn. Nashik.**

Copy s.w.r.t.-

- 1) The Superintending Engineer (Civil) EHV CCCM Circle, Nashik.

Copy to-

- 1) Additional Executive Engineer [Civil] EHV CCCM Sub Division Babhaleshwar.
- 2) Dy. Manager [F&A] Dn. Office, Nashik.
- 3) Master File/Notice Board.



**MAHARASTRA STATE ELECTRICITY TRANSMISSION CO. LTD**  
**EHV CIVIL CONSTRUCTION DIVISION, NASHIK**

Name of work:-Various civil maintenance work in 33 KV yard and colony at 132 KV Rahuri Sub station, Tal:- Rahuri, Dist:- Ahmednagar

**SCHEDULE 'B'**

No.	Description of Item	Quantity	Unit	Rate	GST 18 %	Total	Amount
1	Supplying stone dust of trap stone aggregate in the yard including conveying and stacking etc. complete Spec. No.: Rd. 41 Page No. 215	40.00	Cum	1484.00	267.12	1751.12	70044.80
2	Spreading and conveying the stone dust/murum manually in Electrical live switchyard this includes loading the stone dust/murum, unloading the stone dust/murum and conveying the stone dust/murum upto 50 to 300 m and spreading uniformly as per the thickness inform by th Engineer Incharge etc. completed.	40.00	Cum	167.00	30.06	197.06	7882.40
3	Spreading and conveying the 20/40 mm metal manually in Electrical live switchyard this includes loading the 20/40 mm metal, unloading the 20/40 mm metal and conveying the 20/40 mm metal upto 50 to 300 m and spreading uniformly as per the thickness inform by th Engineer Incharge etc. completed.	460.00	Cum	179.00	32.22	211.22	97161.20
4	Providing and laying in trenches 15 mm dai. CPVC pipe including necessary excavation, fittings. Refilling trenches etc. complete Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	50.00	Rmt	268.00	48.24	316.24	15812.00
5	Providing and laying in trenches 20 mm dai. CPVC pipe including necessary excavation, fittings. Refilling trenches etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	94.00	Rmt	303.00	54.54	357.54	33608.76
6	Providing and laying in trenches 25 mm dai. CPVC pipe including necessary excavation, fittings. Refilling trenches etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	112.00	Rmt	404.00	72.72	476.72	53392.64
7	Providing and laying in trenches 40mm dai. CPVC pipe including necessary excavation, fittings. Refilling trenches etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	5.00	Rmt	569.00	102.42	671.42	3357.10
8	Providing Hydraulic Excavator Wheeled (8 to 10 T JCB) for excavation, levelling, removing small...etc and carrying out the work as per the instruction of engineer Incharge etc comp	1.00	Hour	1129.00	203.22	1332.22	1332.22
9	Conveying materials obtained from excavation / cutting including all lifts, laying in layers 20 cm to 30cm, breaking clods, dressing to the required lines, curves, grades and section for a lead of over 300m. to 500m from the site of excavation to the site of deposition as directed. Spec. No.: MORTH 305	2.00	Cum	182.00	32.76	214.76	429.52
10	Providing and laying Brick curbing including necessary excavation fixing in line and level all labour ,white washing etc. complete as directed by Engr.-in charge.	300.00	Rmt	90.00	16.20	106.20	31860.00
11	Providing and fixing PVC Aqua kraft type super bib tap 15 mm dia. screw including necessary socket union nut complete.	50.00	Cum	352.00	63.36	415.36	20768.00
12	Providing and fixing screw down for 20 mm dia. wheeled stop tap of brass including necessary sockets/union nut complete.	1.00	No.	642.00	115.56	757.56	757.56
13	Providing and fixing screw down for 25 mm dia. wheeled stop tap of brass including necessary sockets/union nut complete.	1.00	No.	832.00	149.76	981.76	981.76
14	Providing and fixing screw down for 40 mm dia. wheeled stop tap of brass including necessary sockets/union nut complete.	1.00	No.	1123.00	202.14	1325.14	1325.14
15	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.5 m.) By Mechanical Means	2.00	Cum	205.00	36.90	241.90	483.80
16	Providing dry/ trap/ granite/ quartzite/ gneiss rubble stone soling 15 cm to 20 cm thick including hand packing and compacting etc. complete.	2.00	Cum	2360.00	424.80	2784.80	5569.60



S.No.	Description of Item	Quantity	Unit	Rate	GST 18 %	Total	Amount
17	Providing and laying Cast in situ/Ready Mix cement concrete in M-10 of trap/ granite/ quartzite/ gneiss metal for foundation and bedding including bailing out water, Steel centering, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing if required and curing complete, with fully automatic micro processor based PLC with / without SCADA enabled reversible Drum Type mixer/concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)	2.00	Cum	6494.00	1168.92	7662.92	15325.84
18	Providing and laying Cast in situ/Ready Mix cement concrete M-15 of trap/ granite/quartzite/gneiss metal for coping to plinth or parapet, moulded or chamfered as per drawing or as directed including steel centering, plywood/ steel formwork compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.) With fine aggregate (Crushed sand VSI Grade)	0.50	Cum	7100.00	1278.00	8378.00	4189.00
19	Providing and fixing in position TMT - FE - 500 bar reinforcement of various diameters for R.C.C. pile caps, footings, foundations, slabs, beams columns, canopies, staircase, newels, chajjas, lintels pardis, copings, fins, arches etc. as per detailed designs, drawings and schedules. including cutting, bending, hooking the bars, binding with wires or tack welding and supporting as required complete.	0.10	M.T	76121.00	13701.78	89822.78	8982.28
20	Providing and constructing Brick Masonry Inspection Chamber 90cm x 45cm x 90cm including 1:4:8 cement concrete foundation 1:2:4 cement concrete channels half round G.S.W.pipes, Brick Masonry, plastering from inside and with frame fixed in cement concrete with R.C.C. Cover medium duty 140Kilogramwith frame etc complete.	1.00	No.	10555.00	1899.90	12454.90	12454.90
21	Providing internal cement plaster 12 mm thick in a single coat using Ready to use wall plaster to concrete or brick surface in all positions including scaffolding and curing complete. Providing groove at joint of B.B. Masonry and concrete members complete. b) cement ratio 1:4 With Prior Approval of Concerned S.E.	180.00	Sqm.	259.00	46.62	305.62	55011.60
22	Providing internal cement plaster 20mm thick in a single coat using Ready to use wall plaster to concrete, brick surfaces in all positions including scaffolding and curing. Providing groove at joint of B.B.Masonry and concrete members complete. b) cement mortar 1:4 With Prior Approval of Concerned S.E.	2.00	Sqm.	486.00	87.48	573.48	1146.96
23	Providing and applying two coats of textured synthetic paint of approved shade and quality and one coat of primer before applying textured paint including scaffolding if necessary preparing surface by thoroughly cleaning oil, grease, dirt and other materials as required, etc. complete.	406.00	Sqm.	157.00	28.26	185.26	75215.56
24	Removing rich mix cement concrete including stacking the spoils as directed with all leads, lifts etc, complete.	2.00	Cum	929.00	167.22	1096.22	2192.44
25	Dismantling brick masonry in lime or cement mortar and stacking the materials as directed with all leads, lifts etc.	2.00	Cum	334.00	60.12	394.12	788.24
26	Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in superstructure including striking joints, raking out joints, watering and scaffolding etc. Complete	1.00	Cum	8451.00	1521.18	9972.18	9972.18
27	Providing & laying prestressed concrete Cable trench covers 75 mm thick with 8 nos of 4 mm dia. HT wire & casting with M400 grade CC using contractor's own cement & compacted with 30MT hydraulic press machine incl. all taxes, loading, unloading transportation and placing them on cable trenches with all lead and lifts etc. complete. as directed by Engr In charge.	19.40	Sq.M.	1776.00	319.68	2095.68	40656.19
28	Providing and fabricating structural steel work in rolled sections, fixed with connecting plates or angle cleats in main and cross beams, hip and jack rafters, purlins connecting to truss members and the like, as per detailed designs and drawing or as directed including cutting, fabricating, hoisting, erecting, fixing in position, making riveted/ bolted/ welded connections and one coat of anticorrosive paint and over it two coats of oil painting of approved quality and shade etc. complete.	0.10	M.T	90763.00	16337.34	107100.34	10710.03
29	Providing & fixing in position french of Infinity Basic design Double / three panel french door with Main frame and SS aldrop or its equivalent includes SS finished tower bolt, Handle, Aldrop , 3.5mm clear glass, with square Bright bar of 10 sq.mm with 100 mm bar spacing & GI sheet 1mm (Jindal 120 gsm	5.00	Sqm.	6163.00	1109.34	7272.34	36361.70



No.	Description of Item	Quantity	Unit	Rate	GST 18 %	Total	Amount
30	Providing and fixing in position powder coated aluminium louvered windows / ventilator of various sizes with powder coating as per detailed drawing and specifications including aluminium frames 80 x 38 mm x 1.22 mm box type, 5 mm thick sheet glass louvers, of approved quality etc. complete.	1.00	Sqm.	3295.00	593.10	3888.10	3888.10
31	Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:4 in half brick thick wall including mild steel longitudinal reinforcement of 2 bars of 6 mm diameter / 2 hoop iron strips 25 mm X 1.6 mm placed at every third course, properly bent and bonded at ends scaffolding, racking out joints and watering etc. complete.	0.50	Sqm.	1133.00	203.94	1336.94	668.47
32	Providing and laying damp proof course 50 mm thick in M20 cement concrete layer and bitumen / using cement with waterproofing compound curing, formwork etc. complete.	1.00	Sqm.	428.00	77.04	505.04	505.04
33	Providing cement based water proofing treatment to terraces (Indian water proofing or alike) with brick bats laid in required slope to drain the water for any span after cleaning the base surface. Applying a coat of cement slurry admixed with approved water proofing compound and laying the brick bats on bottom layer in C.M. 1:5 admixed with approved water proofing compound filling up to half depth of brick bats, curing this layer for 3 days, applying cement slurry over this layer joints of brick bats with C.M. 1:3 admixed with approved water proofing compound and finally top finishing with average 20 mm. thick layers of same mortar added with jute fiber at 1 Kilogram per bag including finishing the surface smooth with cement slurry admixed with approved water proofing compound. Marking finished surface with false squares of 300mm x 300 mm. making the junctions at the parapet rounded and tapered top for required height, with drip mould at the junction of plaster and parapet and curing and covering 10 years Guarantee against leakproofness on Court fee stamp paper of Rs. 500/- including ponding test etc. complete.	1.00	Sqm.	1145.00	206.10	1351.10	1351.10
34	Removing the existing cement plaster of any thickness without causing dust nuisance and stacking the debris upto a distance of 50 metres or spreading in the compound and cleaning the site etc. complete.	5.00	Sqm.	52.00	9.36	61.36	306.80
35	Providing and laying matt finish ceramic tiles of having size 30 cm x 30 cm confirming to I.S. 15622/2006 (group D II-A) and 7 to 8 mm thick for flooring in required position laid on a bed of 1:4 cement mortar including cement float, filling joint with white/colour cement slurry cleaning curing etc. complete.	4.00	Sqm.	1237.00	222.66	1459.66	5838.64
36	Providing and laying ceramic tiles of having size 30 cm. x 30 cm. and confirming to corresponding I.S. for dado and skirting in required position with readymade adhesive mortar of approved quality on plaster of 1:2 cement mortar including joint filling with white/ colour cement slurry cleaning curing etc. complete.	12.00	Sqm.	1310.00	235.80	1545.80	18549.60
37	Scrapping the old plastered internal surface with sand paper and coating the entire surface with mixture of whiting or glue and linseed oil including scaffolding etc. complete as directed.	154.00	Sqm.	36.00	6.48	42.48	6541.92
38	Providing and applying Two coats of wall care Putty on plastered surface and Ceiling and Walls to prepare surface even and smooth of approved make, etc complete.	154.00	Sqm.	92.00	16.56	108.56	16718.24
39	Providing and applying plastic emulsion paint of approved quality, colour and shade to old and new surfaces in two coats including scaffolding, preparing the surface. (excluding the primer coat)etc. complete.	154.00	Sqm.	74.00	13.32	87.32	13447.28
40	Providing and laying vitrified mirror / glossy finish tiles decorative type having size 590 mm to 605 mm x 590 mm to 605 mm of 8 to 10 mm thickness and confirming to IS. 15622-2006 ( group Bla) of approved make, shade and pattern for flooring in required position laid on a bed of 1:4 cement mortar including neat cement float, filling joints, curing and clearing etc. complete.	37.00	Sqm.	1241.00	223.38	1464.38	54182.06
41	Providing and laying vitrified mirror / glossy finish tiles having size 590 mm to 605 mm x 590 mm to 605 mm of 8 to 10 mm thickness and confirming to IS. 15622-2006 ( group Bla) of approved make, shade and pattern for dado and skirting in required position fixed in 1:4 cement mortar including neat cement float, filling joints, curing and clearing etc. complete	3.00	Sqm.	1317.00	237.06	1554.06	4662.18
42	Providing and laying telephone black / Amba White / Cadburybrown / Ruby red / Ocean Brown granite stone of 18 to 20 mm thick for door frame/ dado/ window boxing etc. On C.M. 1:6 including filling joints with polymer base filler nosing/moulding the sharp edges wherever necessary, curing, etc. complete.	3.00	Sqm.	4617.00	831.06	5448.06	16344.18



No.	Description of Item	Quantity	Unit	Rate	GST 18 %	Total	Amount
43	Providing and fixing in position (as per 1868 / 1982) Aluminium sliding window of three tracks with rectangular pipe 95 x 38.10 x 0.90 mm at weight 0.637 Kilogram/Running metre. with window frame bottom track section 92 x 31.75 x 1.30 mm at weight 1.070 Kilogram/Running metre.. Top and side track section 92 x 31.75 x 1.30 mm at weight 0.933 Kilogram/Running metre. The shutter should be of bearing bottom 40 x 18 x 1.25 mm at weight 0.417 Kilogram/Running metre. Inter locking section 40 x 18 x 1.10 mm at weight 0.469 Kilogram/Running metre. and handle and top section 40 x 18 x 1.25 mm at weight 0.417 Kilogram/Running metre. As per detailed drawings and as directed by Engineer incharge with all necessary Aluminium sections fixtures and fastenings such as roller bearing in nylon casting and self locking catch fitted in vertical section of shutter including 5 mm thick plain glass and aluminium mosquito net shutter with stainless steel jail with all required screws and nuts etc, complete. With powder coating without box	8.00	Sqm.	5158.00	928.44	6086.44	48691.52
44	Providing and fixing solid core flush door shutter commercial in single leaf 32 mm thick without ventilator commercial type of exterior grade as per detailed drawings with wrought iron hold fast, stainless steel fixtures and fastenings and handles on both sides and finishing with oil painting 3 coats complete.	8.00	Sqm.	2812.00	506.16	3318.16	26545.28
45	Providing and fixing 30mm thick SOLID PANEL PVC INTERNAL DOOR SHUTTER consisting of frame made out of M.S. tubes of 19 gauge thickness and size of 40mm x 20mm for stiles ,top, lock and bottom rails. M.S. frame shall have a coat of steel primers of approved make and manufacture. M.S. frame shall be covered with 5mm thick heat molded PVC channel of size 30 x 100mm forming stiles, and 5mm thick, 125mm wide PVC sheets for top rail, lock rail and bottom rail on either side, and 15mm (5mm x 3) thick, 20mm wide cross PVC sheet as gap insert for top rail and bottom rail. Paneling of 10 mm thick prelam PVC sheet to be fitted in the M.S. frame welded / sealed to the stiles and rails with 30mm wide x 5mm thick PVC sheet beading on either side, and joined together with solvent cement adhesive etc. An additional 5mm thick PVC strip of 20mm width is to be stuck on the interior side of the C Channel using PVC solvent cement adhesive. including stainless steel fixtures and fastening Complete as per direction of Engineer incharge, manufacturer's specification and drawing.	3.50	Sqm.	6223.00	1120.14	7343.14	25700.99
46	Providing and fixing mild steel grill work for windows, ventilators etc. 20 Kilogram/Square Metre as per drawing including fixtures, necessary welding and painting with one coats of anticorrosive paint and two coats of oil painting complete.	2.00	Sqm.	1957.00	352.26	2309.26	4618.52
47	Providing and fixing 8 cm rigid PVC Nahani trap including PVC grating ,bend, connecting piece of UPVC pipe up to the outside face of wall ,making the good damaged surface and testing etc. complete ( Prior approval of sample and brand by Ex. Engr. is necessary before use)	1.00	No.	523.00	94.14	617.14	617.14
48	Providing and fixing Orissa type white glazed earthenware 575 mm water closet pan including S trap with earthenware foot rests, cast iron soil and vent pipe upto outside face of the wall 1:2:4 brick bat lime concrete bedding without flushing tank and its accessories etc. complete.	1.00	No.	3968.00	714.24	4682.24	4682.24
49	Replacement of damaged Tower Bolt 300 mm Chromium plated of approved quality and make to door/window shutter including removing existing the same in original position making proper adjustment for smooth operation etc. complete as per sample approved by Engineer in-charge.	1.00	No.	182.00	32.76	214.76	214.76
50	Removing doors and windows with frames and stacking the materials as directed with all leads, lifts etc. complete.	11.00	No.	156.00	28.08	184.08	2024.88
51	Providing service of Carpenter skilled on daily basis as per requirement of Engineer Incharge and carrying out the work as directed etc complete	1.00	No	748.00	134.64	882.64	882.64
52	Providing service of Painter skilled on daily basis and as per requirement of Engineer Incharge and carrying out the work etc complete	1.00	No	748.00	134.64	882.64	882.64
53	Providing service of Mazdoor unskilled (heavy male) on daily basis and as per requirement of Engineer Incharge and carrying out the work as directed etc complete	5.00	No	676.00	121.68	797.68	3988.40
54	Providing and constructing Brick Masonry Inspection Chamber 60cm x 45cm x 90cm including 1:4:8 cement concrete foundation 1:2:4 cement concrete channels half round G.S.W. pipes, Brick Masonry, plastering from inside and with frame fixed in cement concrete with R.C.C. Cover medium duty 140Kilogramwith frame etc complete.	1.00	No.	8722.00	1569.96	10291.96	10291.96



No.	Description of Item	Quantity	Unit	Rate	GST 18 %	Total	Amount
55	Cleaning of existing water tank by using detergent including all labor etc complete as directed. a) Capacity upto 1000 ltrs	1.00	No.	599.00	107.82	706.82	706.82
56	Providing and fixing white glazed earthenware Wash Hand Basin of 55cm. x 40 cm. size including cold water pillar tap/cold and hot water pillar tap brackets, rubber plugs and brass chain, stop tap and necessary pipe connections including P.V.C. waste pipe and trap up to the outside face of the wall. Making good the damaged surface, testing etc. complete.	1.00	No.	5646.00	1016.28	6662.28	6662.28
57	Providing and constructing granite kitchen platform with fixing of stainless steel sink 600 mm x 450 mm size as per detailed drawing including vertical both side polished kadappah stone 25 to 30 mm thick supports with kadappah top 35 to 40 mm thick and polished granite 16 to 20 mm top with side strips of granite at front and both sides of platform raised with two vertical granite supports 15 cm height and top granite of 75 x 40 cm including cutting, opening for sink of required size in kadappah as well as granite etc. complete. (Platform top size 5.00 m x 0.60 m and height is 0.75 m)	2.00	Sqm.	10260.00	1846.80	12106.80	24213.60
58	Providing and fixing 8 cm rigid PVC Nahani trap including PVC grating ,bend, connecting piece of UPVC pipe up to the outside face of wall ,making the good damaged surface and testing etc. complete ( Prior approval of sample and brand by Ex. Engr. is necessary before use)	1.00	No.	523.00	94.14	617.14	617.14
59	Providing and fixing H.D.P container Syntex or alike one piece moulded water tank made out of high density polythylene and built corrugated inclusive of delivery up to destination hoisting and fixing of accessories such as inlet,outlet overflow pipe inclusive of all tanks capacity between 200 to 1000 liters	1000.00	Litre	14.00	2.52	16.52	16520.00
60	Providing & placing in position 600 mm dia 450 mm long RCC pipe NP-2 Class as Collar for earth pit including loading unloading etc. complete as directed by Engineer in Charge	49.00	No.	956.00	172.08	1128.08	55275.92
61	Providing, laying and fixing PVC pipe of 90 mm dia 4 kg/cm <sup>2</sup> pressure(class II).in trenches with necessary excavation to required depth with fittings such as bends, tees, reducers, clamps, etc. including necessary excavation, trench filling etc. complete.as directed by Engr In charge.	5.00	Rmt	378.00	68.04	446.04	2230.20
62	Providing and Fixing the MIPATEX HDPE Geo membrane 500 Micron etc.	10.00	Sqm.	103.00	18.54	121.54	1215.40
63	Providing & fixing plain / obscured glass panes 3 mm thick for all sizes including putty/cctw beading or clamps etc. complete.	2.00	Sqm.	455.00	81.90	536.90	1073.80
						<b>Total Rs.</b>	<b>998433.16</b>
						<b>Say Rs.</b>	<b>998433.00</b>

  
**Executive Engineer (Civil)**  
**EHV CCCM Dn Nashik.**

I / We hereby agree to carryout the above work as under :-

- a) At estimated cost.  
b) Above.....% in words.....Of Estimated cost in Schedule "B"  
c) Below.....% in words.....Of Estimated cost in Schedule "B"

I/ We have read the instructions and the same are binding on me / us.

Signature of the Contractors & Address.