

**MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO.LTD.**

(CIN No. U40109MH2005SGC153646)

From:- Executive Engineer (Civil)

EHV Civil Construction cum Maintenances Division Nashik

“Administrative Building” ,Block No. 6, 1<sup>st</sup> floor, Racca Plot,  
Old Saikheda Road, Jail Road, Nashik Road-422 101.

Ph No.:-0253-2403101 (O), Extension Phone No, 0253-2403110

E-Mail ID :ee5710@mahatransco.in Website: www.mahatransco.in

Ref . No. EEC/EHV/CCCM Dn/NSK/Tech- **No - 4 1 5** - Date:- **11 APR 2022**

**e- Quotation**

Sealed and superscripted e- quotations are invited for the work of “**Renovation of Control Room, BCRs and store shed and miscellaneous civil works at 220 KV Pimpalgaon Sub station, Dist:- Nashik.**” As detailed in schedule “B” is enclosed herewith subject to following terms and conditions.

**Name of Work:-** Renovation of Control Room, BCRs and store shed and miscellaneous civil works at 220 KV Pimpalgaon Sub station, Dist:- Nashik.

The quotations should reach to this office on or before **18/04/2022** up to 15.00 Hrs

- 1) The rates [percentage] should be quoted on Firm Quotation basis (Two Bid System only) including cost of materials, labours & T&P etc. required for execution of the work.

**(a) Compulsory Primary Documents in 1<sup>st</sup> Envelop:(Technical Bid)**

- (i) Valid Certificate of Registration of appropriate class for Civil works from PWD /MES/ Railways/ Jeevan Pradhikaran ETC.OR From Any Govt. / Central Government and registered vendor of MSETCL.
- (ii) GST/ GSTIN Registration Certificate.
- (iii) PAN Card
- (iv) E.P.F. Registration Certificate – issued by competent authority of Govt.
- (v) Experience of having successfully completed similar civil works.
- (vi) Payment of EMD Rs. 10000.00 to be made by bidder upto 14.00 hrs of **18/04/2022** in the office of EE(C), Dn., Nashik. EMD details Amount and M.R. No. should be super-scribed on the Envelope & having registered vendor of MSETCL.

**(b) Documents in 2<sup>nd</sup> Envelop:(Price Bid)**

- i) Price bid only where in the rates/percentage should be quoted in figures as well as in words.


**NOTE:- Envelop No.2 (Price Bid) will be opened after qualifying in (Technical Bid) Envelop No.1**

- 2) The quantities enumerated in here attached Schedule B are approximate, however the payment will be made against actual executed quantities on site.



- 3) The work should be completed within **15 days** from the date of handing over the site to commence the work, failing of which a penalty at  $\frac{1}{2}\%$  per week subject to the maximum 10% of the ordered value will be imposed.
- 4) The work should be strictly carried out as per standard specifications & up to the entire satisfaction of the Engineer-in-charge.
- 5) No materials will be supplied by the MSETCL for this work except materials as shown in Schedule A
- 6) Payment will be made through First & Final bill/ R.A. bill basis at the discretion of undersigned.
- 7) The contractor will have to pay security deposit to this office equal to 5% of the ordered value.
- 8) In case any accident occurred to the Contractor's labour/workmen during execution of work, the contractor will be fully responsible for all claims & compensation. No charge in any case will be borne by the MSETCL
- 9) The materials to be utilized for the work should be getting approved from the Engineer-in-charge prior to its utilization for the work.
- 10) The terms & conditions enumerated in the approved Booklet "TENDER AND CONTRACTOR FOR WORKS" will be applied in this case & will be binding on the contractor entirely.
- 11) Right to accept any or to reject any or all the quotations without assigning any reason there of is reserved by the undersigned.
- 12) Payment will be released to agency as per availability of funds. Further MSETCL will not pay any compensation due to non availability of funds.

Yours faithfully,



(V. M. Dhore)

**Executive Engineer (Civil)**  
**EHV Civil CCM Dn. Nashik.**

Copy s.w.r.t.-

- 1) The Superintending Engineer (Civil) EHV CCCM Circle, Nashik.

Copy to-

- 1) Additional Executive Engineer [Civil] EHV CCCM Sub Division Nashik-II.
- 2) Dy. Manager [F&A] Dn. Office, Nashik.
- 3) Master File/Notice Board.



**MAHARASTRA STATE ELECTRICITY TRANSMISSION CO. LTD**  
**EHV CIVIL CONSTRUCTION DIVISION, NASHIK**

Name of work: Renovation of Control Room, BCRs and store shed and miscellaneous civil works at 220 KV Pimpalgaon Sub station, Dist:- Nashik.

**SCHEDULE 'B'**

Sr No.	Description	Qty	Unit	Rate without GST	GST 18%	Rate with GST	Amount
1	Supplying hard murum/ kankar at the road site, including conveying and stacking complete.	25.000	Cubic Metre	624.24	112.36	736.60	18,415.00
2	Spreading hard murum/ soft murrum/ gravel or kankar for side width complete	25.000	Cubic Metre	74.74	13.45	88.19	2,204.75
3	Compacting the hard murum side widths including laying in layers on each side with vibratory roller including artificial watering etc. complete.	250.000	Square Metre	19.19	3.45	22.64	5,660.00
4	Supplying 20 mm. size machine crushed trap stone metal free from impurities etc. as directed by Engineer – in – charge in the switch yard including conveying and stacking etc. complete with all leads and lifts. (Stack measurement will be paid)	50.000	Cubic Metre	1,644.53	296.02	1,940.55	97,027.50
5	Spreading 20 mm. and 40 mm. size stone metal within 100 meters distance by head loading including leveling etc. complete as directed.	50.000	Cubic Metre	74.74	13.45	88.19	4,409.50
6	Providing and laying in trenches 40mm dai. CPVC pipe including necessary excavation, fittings. Refilling trenches etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	2.000	Runnin g Metre	542.37	97.63	640.00	1,280.00
7	Providing and laying in trenches 25 mm dai. CPVC pipe including necessary excavation, fittings. Refilling trenches etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	3.000	Runnin g Metre	384.81	69.27	454.08	1,362.24
8	Providing and laying in trenches 20 mm dai. CPVC pipe including necessary excavation, fittings. Refilling trenches etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	5.000	Runnin g Metre	288.86	51.99	340.85	1,704.25
9	Providing and laying in trenches 15 mm dai. CPVC pipe including necessary excavation, fittings. Refilling trenches etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	25.000	Runnin g Metre	255.53	46.00	301.53	7,538.25
10	Providing and fixing 40 mm screw down wheeled stop tap of brass including necessary sockets / union nut, testing etc. complete. (Prior approval of sample and brand by Ex. Engineer is necessary before use.) Spec. No. : Bd.V.9 Page No. 555	2.000	Numbe r	1,069.59	192.53	1,262.12	2,524.24
11	Providing and fixing 25 mm screw down wheeled stop tap of brass including necessary sockets / union nut, testing etc. complete. (Prior approval of sample and brand by Ex. Engineer is necessary before use.) Spec. No. : Bd.V.9 Page No. 555	2.000	Numbe r	792.85	142.71	935.56	1,871.12
12	Providing and fixing 15 mm diameter screw down bibcock (Standard) of symet type including necessary sockets, union nut, testing etc. complete. (Prior approval of sample and brand by Ex. Engineer is necessary before use.) Spec. No. : Bd.V.8 / Page No. 554	20.000	Numbe r	643.37	115.81	759.18	15,183.60
13	Providing and laying Brick curbing including necessary excavation fixing in line and level all labour ,white washing etc. complete as directed by Engr.-in charge.	315.000	Runnin g Metre	70.70	12.73	83.43	26,280.45
14	Providing and fixing in position TMT - FE - 500 bar reinforcement of various diameters for R.C.C. pile caps, footings, foundations, slabs, beams columns, canopies, staircase, newels, chajjas, lintels pardis, copings, fins, arches etc. as per detailed designs, drawings and schedules. including cutting, bending, hooking the bars, binding with wires or tack welding and supporting as required complete.	0.010	Metric Tonne	72,495.78	13,049.24	85,545.02	855.45



Sr No.	Description	Qty	Unit	Rate without GST	GST 18%	Rate with GST	Amount
15	Providing unskilled labours for various works as directed by Engineer-in-charge etc complete	20.000	Day	584.79	105.26	690.05	13,801.00
16	Clearing grass and removal of rubbish up to a distance of 50 metres outside the periphery of the area .	20,200.000	Square metre	4.04	0.73	4.77	96,354.00
17	Conveying of materials outside premise of substation or to the location as directed by engineer etc complete	60.000	Cubic metre	190.89	34.36	225.25	13,515.00
18	Providing and laying vitrified mirror / glossy finish tiles having size 590 mm to 605 mm x 590 mm to 605 mm of 8 to 10 mm thickness and confirming to IS. 15622-2006 ( group Bla) of approved make, shade and pattern for dado and skirting in required position fixed in 1:4 cement mortar including neat cement float, filling joints, curing and clearing etc. complete	10.920	Square metre	1,247.80	224.60	1,472.40	16,078.61
19	Providing and applying two coats of water proof cement paint of approved manufacture and of approved colour to old plastered surfaces including scaffolding if necessary, cleaning and preparing the surface, watering for two days etc. complete.	5.000	Square metre	73.73	13.27	87.00	435.00
20	Providing and applying two coats of textured synthetic paint of approved shade and quality and one coat of primer before applying textured paint including scaffolding if necessary preparing surface by thoroughly cleaning oil, grease, dirt and other materials as required, etc. complete.	2,491.000	Square metre	149.48	26.91	176.39	439,387.49
21	Scraping out old paint from wall surface to receive new coats of painting and disposing material etc	1,759.000	Square metre	7.07	1.27	8.34	14,670.06
22	Providing and applying Two coats of wall care Putty on plastered surface and Ceiling and Walls to prepare surface even and smooth of approved make, etc complete.	10.000	Square metre	87.87	15.82	103.69	1,036.90
23	Providing and applying priming coat on concrete/ masonry/ Asbestos Cement plastered surfaces including scaffolding if necessary, preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter and sand papering as required etc. complete.	1,759.000	Square metre	34.34	6.18	40.52	71,274.68
24	Providing and applying plastic emulsion paint of approved quality, colour and shade to old and new surfaces in two coats including scaffolding, preparing the surface. (excluding the primer coat)etc. complete.	1,759.000	Square metre	70.70	12.73	83.43	146,753.37
Total Rs.							999,622.46
Say Rs.							999,622.00

Executive Engineer (Civil)  
EHV CCCM-Dn Nashik.

I / We hereby agree to carryout the above work as under :-

- At estimated cost.
- Above.....% in words.....Of Estimated cost in Schedule "B"
- Below.....% in words.....Of Estimated cost in Schedule "B"

I/ We have read the instructions and the same are binding on me / us.

Signature of the Contractors & Address.