

**- OFFICE OF THE -  
EXECUTIVE ENGINEER (C)**

EHV Civil Constn. Cum Maintenance Division,  
Mahatransco Administration Building, first Floor,  
wing no.102, Aurangabad, Ph. No. (0240) 2331429,  
E-mail : ee2710@mahatransco.in CIN: U40109MH2005SGC153646



No.: EEC/EHV/CCCM/Dn./ABD//Tech/

**No 0 0 4 2 9**

Date:-

**0 4 MAY 2022**

**e- Quotation Enquiry**

To,

**Sub:** Construction of RCC culverts at 132 kV S/S Paithan, Aurangabad.

**Dear Sir,**

Sealed percentage rate quotations are invited from Govt. registered & experienced Contractors for the above work as per schedule enclosed. The quotation should reach to the office of Executive (Civil) EHV CCCM Division Aurangabad on or **before dated 17.05.2022 Time 16.30 Hrs.**


**TERMS AND CONDITIONS:**

- 1) The work should be carried out as per P.W.D. specification and instructions of the Engineer in-Charge and to the satisfaction of the undersigned.
- 2) The quantities mentioned in the attached schedule are approximate and likely to vary. However, payment will be made as per the work actually executed and measured. The rates shown in enclosed schedule B are inclusive of GST.
- 3) The work should be completed within **(40)** days from the date handing over the site, failing which the contractor shall be liable to pay as compensation an amount equal to one percent or such similar amount as the competent authority may decide of the W.O. cost for every day the work remain unfinished after due date of completion subject to the maximum 10% of the cost of the order.
- 4) The work which is of bad workmanship quality will not be measured and paid.
- 5) Contractor shall have to arrange for require cement, steel etc. at his own cost without involving any financial implications to MSETCL.
- 6) Other material such as required tools and plant will have to arrange by the contractor at his own cost.
- 7) The water arrangement will have to be made by the contractor at his own cost. And it is not binding on the part of department to provide water for the work. In case in water is supplied by Department, then the water will be charged at the rate 1% of work done for water consuming item or 0.25% of total value of work order as decided by the Engineer in-charge.
- 8) The contractor will have to make good the damages if any made by him during the execution of work at his own cost.
- 9) The material should be got approved prior to fixing from the Engineer in-charge.
- 10) Income Tax as per the prevailing income Tax rule and subsequent amendment thereof will be recovered at source of your bill on total value of work done for which the certificate will be issued if desired.



- 11) Contractor should submit the purchase vouchers for cement, steel with the bills invariably.
- 12) Contractor will be held responsible for accident occurred during the course of the work and will have to pay the compensation as per the act 1923 and subsequent amendment thereof.
- 13) Contractor should submit his bill in triplicate through Addl. Executive Engineer (Civil) EHV CCCM Sub-Division-I Aurangabad the undersigned. Payment will be made within 60 days period from the date of receipts of bill to this office.
- 14) The terms and conditions in the M.S.E.T. Co. Ltd. Booklet 'Tender and contract work' will stand applicable for this work.
- 15) You will have to deposit 30,000.00 (5% of quotation value) as security deposit in cash or DD of any nationalized Bank within 10 days from the date of receipt or receipt of work order, failing which EMD paid will stand forfeited.
- 16) The contractor's offer will be considered as inclusive of all taxes and charges and it will be the contractor's responsibility to pay the taxes to Government and same will not be reimbursed to the contractor.
- 17) Your own rates should be quoted in words and figures scratches and over written rates shall not be considered if not initialed.
- 18) The contractor has to pay earnest money to **Rs. 6,000.00/-** in cash/In form of DD of any Nationalized Bank in favor of Executive Engineer (C) EHV CCCM DIV. MSETC Ltd. Aurangabad. The Vendor has necessarily to obtain the receipt of EMD from this office if EMD is paid online or in form of DD and to submit the same alongwith the quotation. If the EMD paid receipt i.e MR of required amount is not found in the envelop the quotation will be rejected. else bid will be rejected.
- 19) The undersigned reserves the right to reject any or all quotations without assigning any reason what so ever.
- 20) GST will be recovered from your bill as per GST norms.
- 21) **Special condition:** The payment shall be effected as per fund availability. Due to shortage of fund there are chances of delay in payments for which the agency will have to bear with the Dept. No. any of claim on this account will be entertained.
- 22) The estimated cost of the work is Rs. **5,56,106.35** only. (Inclusive of all Taxes)
- 23) The Contractor has to submit the Civil Works Registration Certificate, GST Registration and PAN card at the time offer submission as mandatory documents.

**Encl:** Schedule 'B'

  
(J.P. Patil)  
Executive Engineer (C)  
EHV CCCM Division, Aurangabad

**Copy S.W.R.S. to :**

1. The Superintending Engineer (C). EHV CCCM Circle, Aurangabad

**Copy to:**

1. The Dy. Manager (F&A) EHV CCCM Division, Aurangabad
2. I.T Section Zone office Aurangabad-For Publishing on MSETCL Website.
3. Notice Board Division Office Aurangabad.



**- OFFICE OF THE -**

**EXECUTIVE ENGINEER (C)**

EHV Civil Constn. Cum Maintenance Division,  
Mahatransco Administration Building, first Floor,  
wing no.102, Aurangabad, Ph. No. (0240) 2331429,  
E-mail : ee2710@mahatransco.in CIN: U40109MH2005SGC153646



**Name of Work :** Construction of RCC culverts at 132 kV S/S Paithan, Aurangabad.

**Estimated Amount: -** Rs. 5,56,106.35 (Inclusive of All Taxes)

  
Executive Engineer (C)  
EHV CCCM Division, Aurangabad.

**Quotation for Works**

I/We hereby ~~quote~~ for the execution of the specified in the above written memorandum within time specified in such memorandum at (at Figure) .....% above/below/Estimated Rate (in Words) ..... percent above/Below/Estimated rate (to be struck whichever is not applicable) the estimated rates entered in schedule "B" (memorandum showing item of work to be carried out) in accordance in all instruction in writing from the Engineer – in – Charge.

I/We have read the general conditions of contracts & the conditions enumerated in the quotation and the same are binding on us.

**Signature of the contractor**

**Full Address:**




**MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.**  
**EHV CCCM Division, Aurangabad.**  
**Name of work- Construction of RCC culverts at 132 kV S/S Paithan, Aurangabad.**  
**Schedule - B**

As per PWD SSR 2020-21

SR.No	Act. No.	ITEM OF WORK	QTY.	Unit	RATE	Add 18% GST	Rate with GST	AMOUNT
1	50013068	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.5 m.) By Mechanical Means	10.00	Cum	193.19	34.77	227.96	2279.60
2	50013069	Excavation for foundation in hard murum including removing the excavated material upto distance of 50 metres beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.50 m) By Mechanical Means	18.20	Cum.	212.21	38.20	250.41	4557.46
3	50013077	Providing soling using 80 mm size trap metal in 15 cm. layer including filling voids with Crushed sand/grit, ramming, watering etc. complete.	10.92	Cum	1982.07	356.77	2338.84	25540.13
4	50004101	<b>M 15 for PCC</b> Providing and laying Cast in situ/Ready Mix cement concrete in M15 of trap/granite/quartzite/gneiss metal for bed blocks, foundation blocks and such other items including bailing out water, Steel centering, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.), without SCADA complete. With fine aggregate (Crushed sand VSI Grade)	3.64	Cum	5915.91	1064.86	6980.77	25410.00
5	50013153	<b>M20 for Foundation</b> Providing and laying in situ /Ready Mix cement concrete M-20 of trap / granite / quartzite/ gneiss metal for R.C.C. work in foundations like raft, strip foundations, grillage and footings of R.C.C. columns and steel stanchions etc. including bailing out water, Steel centering formwork, laying/pumping cover blocks, compaction and curing roughening the surface if special finish is to be provided (Excluding reinforcement and structural steel) etc. complete, without SCADA complete. With fine aggregate (Crushed sand VSI Grade)	7.00	Cum	7091.64	1276.49	8368.13	58576.91
6	50005520	<b>M20 for Slab</b> Providing and laying Cast in situ/Ready Mix cement concrete M-20 of trap/ granite / quartzite/ gneiss metal for R.C.C. slabs and landings as per detailed designs and drawings including steel centering, formwork, cover blocks, laying/pumping, compaction finishing the formed surfaces with cement mortar 1:3 of sufficient minimum thickness to give a smooth and even surface or roughening if special finish is to be provided and curing etc. Complete, (Excluding reinforcement and structural steel).without SCADA complete. With fine aggregate (Crushed sand VSI Grade)	4.00	Cum	14375.91	2587.66	16963.57	67854.28



7	50005556	<b>M20 for Pardi</b> Providing and laying Cast in situ/Ready Mix cement concrete in M-20 of trap/ granite/ quartzite/ gneiss metal for R.C.C. pardi of required thickness including steel centering, formwork, cover blocks, laying/pumping, compacting, curing, finishing and roughening them if special finish is to be provided and curing complete.(Excluding reinforcement and structural steel).without SCADA complete. With fine aggregate (Crushed sand VSI Grade)	6.00	Cum	15125.66	2722.62	17848.28	107089.68
8	50013181	<b>Providing and fixing in position TMT - FE - 500 bar reinforcement</b> of various diameters for R.C.C. pile caps, footings, foundations, slabs, beams columns, canopies, staircase, newels, chajjas, lintels pardis, copings, fins, arches etc. as per detailed designs, drawings and schedules. including cutting, bending, hooking the bars, binding with wires or tack welding and supporting as required complete.	0.984	MT	71849.78	12932.96	84782.74	83468.30
9	50013129	<b>Providing and fabricating structural steel work in rolled sections</b> like joists, channels, angles, tees etc. as per detailed design and drawings or as directed including cutting, fabricating, hoisting, erecting, fixing in position making riveted / bolted /welded connections without connecting plates, braces etc. and including one coat of anticorrosive paint and over it two coats of oil painting of approved quality and shade etc. complete.	1.56	MT	89270.18	16068.63	105338.81	164749.90
10	50013716	<b>Dismantling brick masonry</b> in lime or cement mortar and stacking the materials as directed with all lead	5.00	Cum	315.32	56.76	372.08	1860.40
11	50014283	<b>Dismantling the R.C.C. Work 1:2:4</b> and sorting out the materials such as steel etc. as directed and stacking them within the specified lead as directed etc. complete.	6.30	Cum	1367.37	246.13	1613.50	10165.05
12	50013979	<b>Providing and laying weep holes of 100 mm diameter PVC pipes</b> as per drawing for abutment returns, return walls etc. Complete.	8.00	Rmt	482.48	86.85	569.33	4554.64
<b>Total =</b>							<b>556106.35</b>	

  
 Executive Engineer ( C )  
 EHV CCCM Division  
 MSETCL Aurangabad