

**MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.**

<b>Name of Office</b>	: Executive Engineer, EHV O&M Division, Latur.
<b>Office Address</b>	: 132 kV Latur(MIDC) S/s Premises, Near Kirti Gold Mill, MIDC Road, Latur-413512
<b>Contact No.</b>	: 02382-222208 (O), 8956304905/8956304912
<b>Email ID</b>	: eelaturdn@gmail.com, ee2220@mahatransco.in.

Ref. No. : EE/EHV/O&M/LTR/TS/ **No 00477** Date: - **30 MAY 2022**  
**E-Enquiry**

**Sub :- E-Enquiry for Work of P&F UPVC Earth Pit Water Pipeline at 132 kV Renapur S/s under EHV O&M Dn, Latur**

**Dear Sirs,**

Sealed and super scribed quotations are invited for the work as specification given below. The quotation giving full particulars should reach this office on or before **07.06.2022**..., up to 15.00 Hrs positively. The Taxation liability should show separately. Rights of cancellation/modification of E-Enquiry at any stage, is reserved at this office.

**Schedule 'A'**

Sr. No.	Particulars	Unit	Qty	Rate/Unit (Excluding GST)	Rate/Unit (Including GST@18%)	Total (Including all Taxes)
1	P&F 40 mm Ø uPVC Pipe 10kg/sqcm Presur Providing and fixing in position 40 mm. Diameter Ultra Violet stabilized UPVC plumbing pipes of specified outer diameter required standard thickness confirming to I.S.. 4985, including necessary fittings confirming to I.S.. 7834, such as P.V.C.. bends, vees, reducers, clamps, plugs etc. necessary excavation trench, refilling, necessary drilling holes in walls / slab, and making the good the surface etc. complete. (For 10.00 Kg/Sq.cm.. pressure)( including defect liability period and bond for three years.)Spec. As directed by Engineer-In-Charge.	RMT	500			



Sr. No.	Particulars	Unit	Qty	Rate/Unit (Excluding GST)	Rate/Unit (Including GST@18%)	Total (Including all Taxes)
2	P&F 25mm Ø uPVC Pipe 10kg/sqcm Presur (Providing and fixing in position 25mm. Diameter Ultra Violet stabilized UPVC plumbing pipes of specified outer diameter required standard thickness confirming to I.S.. 4985, including necessary fittings confirming to I.S.. 7834, such as P.V.C.. bends, vees, reducers, clamps, plugs etc. necessary excavation trench, refilling, necessary drilling holes in walls / slab, and making the good the surface etc. complete. (For 10.00 Kg/Sq.cm.. pressure)( including defect liability period and bond for three years.)Spec. As directed by Engineer-In-Charge.	RMT	350			
4	P&F 15 mm Ø uPVC Pipe 10kg/sqcm Presur Providing and fixing in position 15 mm. Diameter Ultra Violet stabilized UPVC plumbing pipes of specified outer diameter required standard thickness confirming to I.S.. 4985, including necessary fittings confirming to I.S.. 7834, such as P.V.C.. bends, vees, reducers, clamps, plugs etc. necessary excavation trench, refilling, necessary drilling holes in walls / slab, and making the good the surface etc. complete. (For 10.00 Kg/Sq.cm.. pressure)( including defect liability period and bond for three years.)Spec. As directed by Engineer-In-Charge.	RMT	100			
5	P&F 40 mm Ø Brass Wheel Stop Tap Providing and fixing 40 mm dia. screw down bib/stop tap of brass of approved quality and make, including necessary sockets, union nut, testing etc. complete. Spec. No.:BdV.9 Page No.555	No.	15			
6	P&F 25mm Ø Screw Down Whl Tap of Steel Providing and fixing 25mm.dia. screw down wheeled	No.	25			



Sr. No.	Particulars	Unit	Qty	Rate/Unit (Excluding GST)	Rate/Unit (Including GST@18%)	Total (Including all Taxes)
	stop tap of steel with chromium plating of approved quality and make bearing I.S.I. mark, including sockets, union nut complete. Spec. No.:BdV.-9 Page No.555					
8	P&F 15mm Ø SDWhl Tap of Steel Chr Plat Providing and fixing 15mm.dia. screw down wheeled stop tap of steel with chromium plating of approved quality and make bearing I.S.I. mark, including sockets, union nut complete. Spec. No.:BdV.-9 Page No.555	No.	100			
9	P&F 15mm Ø Screw Down Bib Tap of Brass Providing and fixing 15 mm dia. screw down bib/stop tap of brass of approved quality and make, including necessary sockets, union nut, testing etc. complete.Spec. No.:BdV.-8 Page No.554	No.	100			
<b>Grand Total (Including all Taxes)</b>						


**Estimated amount for the above work: Rs. 2,11,592/- (Including all Taxes & Cess)**

**Note:-** 1. Rate of GST shall be mentioned by Bidder on their Offer with SAC Code.

2. No Conditional bid shall be Accepted.

4. Xerox signed copies of below mentioned documents should be attached along with quotation.

- PAN Card.
- GST registration Certificate
- Bombay Shop Act License
- Valid Contractor Electrical License
- Experience certificate of carrying out the simillar work issued by, not below the rank of Executive Engineer

  
 (Prakash D. Jaybhay)  
**Executive Engineer,**  
**EHV O&M Division Latur**