

MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.

Name of Office	: Executive Engineer, EHV O&M Division, Latur.
Office Address	: 132 kV Latur(MIDC) S/s Premises, Near Kirti Gold Mill, MIDC Road, Latur-413512
Contact No.	: 02382-222208 (O), 8956304905/8956304912
Email ID	: eelaturdn@gmail.com, ee2220@mahatransco.in.

Ref. No. : EE/EHV/O&M/LTR/TS/ **NO 00514**

Date: **6 JUN 2022**

E-Enquiry (Second Call)

Sub :- E-Enquiry for Work of Electrical wiring for E-Type Residential Quarters at 132 kV Latur (K) S/s under EHV O&M Dn, Latur

Dear Sirs,

Sealed and super scribed quotations are invited for the work as specification given below. The quotation giving full particulars should reach this office on or before **13.06.2022**, up to 15.00 Hrs positively. The Taxation liability should show separately. Rights of cancellation/modification of E-Enquiry at any stage, is reserved at this office.

Schedule 'A'

Sr No.	Particulars	Unit	Qty	Ex Works	Unit Rate (incl. GST@18%) +Labour Cess	Amount in Rs.
1	Supplying and erecting PVC trunking (PVC casing-n-capping) of size 25 mm with accessories on wall/ceiling as per specification No: WG MA/CON.	mtr	700			
2	Supplying and erecting fresh air cum exhaust fan of light duty 250 V A.C. 50 cycles 300mm. 1400 RPM rust proof body & blades, wire mesh, duly erected in an approved manner.	Each	8			
3	Supplying and erecting five star rated energy saving Ceiling fan 230 V A.C. 50 cycles 1200 mm complete erected in position as per specification no. FG-FN/CF	Each	12			
4	Supplying & erecting ready to use Retrofit T8 LED 18 / 20 tube light with polycarbonate body, heat sink, integrated HF electronic driver complete & compatible to T8 / T12 LED luminaire by disconnecting starter & ballast if necessary.	Each	40			
5	Supplying and erecting Ceiling rose / Batten holder / Slanting holder / hanging cord switch / hanging bell push/pendent holder bakelite base 6A. erected on filled polypropylene board or polished double wooden block/ PVC junction box	Each	120			


Sr No.	Particulars	Unit	Qty	Ex Works	Unit Rate (incl. GST@18%) +Labour Cess	Amount in Rs.
6	Supplying and erecting ISI mark modular type (one module) electronic dimmer 400 / 450W, duly erected on provided plate and box with wiring connections complete.	Each	12			
7	Supplying and erecting 6 to 32 A SPMCB suitable to fix in 1 module of modular switch in provided box complete & duly concealed with necessary material and connected.	no.	8			
8	Supplying, erecting & marking TPN MCB 40A to 63A, C- series in provided distribution board as per specification no. SW-SWR/MCB	no.	16			
9	Supplying & erecting mains with 2x2.5 sq.mm. and earth wire 1.5 sq.mm FR PVC copper wire, in HMS PVC conduit min. 20mm dia, as per specification No: WG-MA/PC.	mtr	600.00			
10	Supplying & erecting mains 2x1.5 sq.mm. and earth wire 1.5 sq.mm FR PVC copper wire, ISI mark HMS PVC conduit min. 20mm dia, as per specification No: WG-MA/PC.	mtr	1200.00			
11	Supplying and erecting single pole and neutral distribution board (SPNDB) with door surface/flush mounted with 2 ways for incoming and 10 ways for outgoing SP MCB's on iron/ G.I. frame/wooden board as per specification No. SW-SWR/MCBDB	nos	16.00			
12	Supplying and erecting PVC Surface modular switch box with double mounting plate for 12 modules duly erected.	Each	16.00			
13	Supplying and erecting PVC Surface modular switch box with double mounting plate for 4 modules duly erected.	Each	16.00			
14	Supplying and erecting ISI mark modular type switch 6A / 10A duly erected on provided plate and box with wiring connections complete	Each	120			
15	Supplying and erecting ISI mark modular type 3 pin 6A multi sockets with safety shutter, duly erected on provided plate and box with wiring connections complete.	Each	50			

Sr No.	Particulars	Unit	Qty	Ex Works	Unit Rate (incl. GST@18%) +Labour Cess	Amount in Rs.
16	Supplying and erecting ISI mark modular type switch 16A duly erected on provided plate and box with wiring connections complete	Each	16			
17	Supplying and erecting ISI mark modular type 3 pin 6 / 16A multi socket with safety shutter, duly erected on provided plate and box with wiring connections complete.	Each	16			
18	Providing earthing with galvanized iron earth plate size 60 x 60 x 0.6 cm complete with all materials, testing & recording the results as per specification no. EA-EP	Each	4			
19	Supply and Erecting LED Street light fitting suitable above 26W to 36 W Lamp, including lamp with PF>0.95 class IP 65 and above housing of pressure die cast aluminium Alloy and heat sink executed aluminium completed as per specification No. FGODF/FL52	Each	12			
Total (Including all Taxes)						

Estimated amount for the above work: Rs. 4,74,832/- (Including all Taxes & Cess)

- Note:-**
1. Rate of GST shall be mentioned by Bidder on their Offer with SAC Code.
 2. No Conditional bid shall be Accepted.
 3. Xerox signed copies of below mentioned documents should be attached along with quotation.
 4. Without Letter-head, No Quotation will be accepted.

- a) PAN Card.
- b) GST registration Certificate
- c) Bombay Shop Act License
- d) Valid Contractor Electrical License
- e) Experience certificate of carrying out the same work issued by, not below the rank of Executive Engineer
- f) The Agency before submission of bid, shall visit the site to inspect the job at Sub-station and submit the Job inspected report, duly signed by Executive Engineer/ S/s Incharge.


Executive Engineer,
EHV O&M Division Latur