

MAHARASHTRA STATE ELECTRICITY TRANSMISSION COMPANY LTD.,
(CIN No. U40109 MH 2005 SFC 153646)

EHV CIVIL CONSTRUCTION CUM MAINTENANCE DIVISION-PARBHANI

EXECUTIVE ENGINEER (Civil)
MSETCL, EHV CCCM Division,
Old Power House Premises, Jintur Road, Parbhani (431 401).
Parbhani Dist :Parbhani -431 401

Tel (O) : **02452-242002** (O)
E-mail :
ee2720@mahatransco.in
Web: www.mahatransco.in

No. EEC/Dn./PBN /Tech/W-68/No. 0296


Date : 13.06.2022

E-Enquiry
QUOTATION NOTICE

The sealed percentage rate quotations are invited for the following works from the Civil Contractors preferably registered with PWD, Railway and such other department or experienced in similar works of equivalent amount in M.S.E.T.C.L Ltd. The quotations should be submitted in the office of The Executive Engineer (Civil) EHV CCCM Division, MSETCL, Parbhani, Old Power House Premises, Jintur Road, Parbhani from 13.06.2022 to on or **before Dated 20/06/2022 (Monday) up to 16.00 Hrs. (Time).**

The required blank quotation to be submitted is attached herewith.

Sr. No.	Name of work	Estimated cost	E.M.D.	Time Limit
1.	The work of construction of retaining wall pardi to tower (Location Number 107) at 132 kv Jangamwadi for 132kv Waghala -Jangamwadi line, Dist. Nanded.	Rs. 2,85,168.00/-	Rs. 2,860.00/-	30 Days



(V.G. Avhad)
Executive Engineer (C) (I/C)
EHV CCCM Dn. Parbhani.

Copy S.W.R.S. To:

1. The Superintending Engineer (C) EHV CCCM Circle, MSETCL, Aurangabad.
...This is as per approval vide Ltr. No. 0634 Dt. 10.06.2022.

Copy To:

1. The I.T. section zone office Aurangabad.
...**For Publication of E-enquiry on MSETCL website.**
2. The Addl. Executive Engineer (C) EHV CCCM Sub Division-I Nanded.
3. The Dy. Manager (F&A), EHV CCM Division, Parbhani.
-The amount of this work is Chargeable to sanctioned estimate No. T-03/ 2022-23 Dt. 13.06.2022.
under R&M Budget.
4. Notice Board.



MAHARASHTRA STATE ELECTRICITY TRANSMISSION COMPANY LTD.,
(CIN No. U40109 MH 2005 SFC 153646)

EHV CIVIL CONSTRUCTION CUM MAINTENANCE DIVISION-PARBHANI

EXECUTIVE ENGINEER (Civil)
MSETCL, EHV CCCM Division,
Old Power House Premises, Jintur Road, Parbhani (431 401).
Parbhani Dist :Parbhani -431 401

Tel (O) : **02452-242002** (O)
E-mail :
ee2720@mahatransco.in
Web: www.mahatransco.in

Date :-

E-enquiry

To,

.....
.....
.....

Subject: The work of construction of retaining wall to tower (at Location Number 107) for 132kv Waghala -Jangamwadi line, Dist. Nanded.

Dear Sir,

The Sealed percentage rate quotations are invited from Govt. registered & experienced Contractors for the above work as per schedule enclosed. The quotation should reach to the office of the Executive Engineer (Civil) EHV CCCM Division, MSETCL, Parbhani, Old Power House Premises, Jintur Road, Parbhani on or **before Dated 20/06/2022 (Monday) up to 16.00 Hrs. (Time).**

TERMS AND CONDITIONS:

- 1) The work should be carried out as per P.W.D. specification and instructions of the Engineer in-Charge and to the satisfaction of the undersigned.
- 2) The quantities mentioned in the attached schedule are approximate and likely to vary. However, payment will be made as per the work actually executed and measured. The rates shown in enclosed schedule B are inclusive of GST.
- 3) The work should be completed within **(30) CALENDER DAYS** from the date handing over the site, failing which the contractor shall be liable to pay as compensation an amount equal to one percent or such similar amount as the competent authority may decide of the W.O. cost for every day the work remain unfinished after due date of completion subject to the maximum 10% of the cost of the order.
- 4) The work which is of bad workmanship quality will not be measured and paid.

- 5) Contractor shall have to arrange for require any equipment, cement, steel etc. at his own cost without involving any financial implications to MSETCL.
- 6) Other material such as require labour, tools and plant will have to arrange by the contractor at his own cost.
- 7) The water arrangement /Electricity will have to be made by the contractor at his own cost and it is not binding on the part of department to provide water /Electricity for the work. In case in water/ Electricity is supplied by Department, then the water /Electricity will be charged at the rate 1% of work done for water/Electricity consuming item or 0.25% of total value of work order as decided by the Engineer in-charge.
- 8) The contractor will have to make good the damages if any made by him during the execution of work at his own cost.
- 9) The material should be got approved prior to fixing from the Engineer in-charge.
- 10) The contractor should submit the purchase vouchers for cement, steel with the bill invariably.
- 11) Income Tax as per the prevailing income Tax rule and subsequent amendment thereof will be recovered at source of your bill on total value of work done for which the certificate will be issued if desired.
- 12) As per corporate office Circular No. 7199 Dt. 30.06.2016, the deduction of the labour cess 1% will be effected from each RA bill and as per any amendment from time to time will be applicable.
- 13) Contractor will be held responsible for accident occurred during the course of the work and will have to pay the compensation as per the act 1923 and subsequent amendment thereof.
- 14) Contractor should submit his bill in triplicate through Addl. Executive Engineer (Civil) EHV CCCM Sub-Division, Parbhani to the undersigned. Payment will be made within 45 days period from the date of receipts of bill to this office.
- 15) The terms and conditions in the M.S.E.T. Co. Ltd. Booklet 'Tender and contract work' will stand applicable for this work.
- 16) You will have to deposit **5.00 %** of quotation value as a security deposit against the amount of work order in cash/ DD of any nationalized Bank within 07 days from the date of receipt of LOI, if you will stand successful bidder, failing which EMD will stand forfeited.
- 17) The contractor's offer will be considered as inclusive of all taxes and charges and it will be the contractor's responsibility to pay the taxes to Government and same will not be reimbursed to the contractor.
- 18) Your own offer should be quoted in words and figures scratches and over written rates shall not be considered if not initialed.
- 19) The contractor has to pay earnest money to **Rs. 2,860.00/-** in cash/RTGS/NEFT/In form of DD of any Nationalized Bank in favor of the EE (C), EHV CCCM DIVISION, MSETC Ltd. PARBHANI. If the EMD receipt of required amount is not found in an envelope, quotation will be rejected.
- 20) The undersigned reserves the right to reject any or all quotations without assigning any reason what so ever.
- 21) GST will be recovered from your bill as per GST norms.

- 22) **Special condition:** The payment shall be effected as per fund availability. Due to shortage of fund there are chances of delay in payments for which the agency will have to bear with the Dept. No. any of claim on this account will be entertained.
- 23) The estimated cost of the work is **Rs. 2,85,168.00** /- only. (Inclusive of all Taxes)
- 24) As per revised circular issued by Dy. Directorate of Insurance Maharashtra State, the contractor shall, apart from other relevant insurance, submit labour insurance @ 1% of contract value to EHV CCCM Division Parbhani before starting of the work. The insurance cover shall be procured by the contractor from Director of insurance Govt, Insurance Fund, Govt of Maharashtra or from United India Insurance Company. Ltd.
- 25) Contractor has to submit the valid registration, Work Experience of similar work under Govt. body, GST registration certificate, EMD Paid Receipt as mandatory documents at the time of submission of Quotation.
- 26) The rates should also be submitted on Separate letter head of agency in addition to above all.

Encl. : Schedule 'B'


Executive Engineer (C)
EHV CCCM Dn. Parbhani.

Copy S.W.R.S. To :

1. The Superintending Engineer (C) EHV CCCM Circle, MSETCL, Aurangabad.
...This is as per approval vide Ltr. No. 0634 Dt. 10.06.2022.



MAHARASHTRA STATE ELECTRICITY TRANSMISSION COMPANY LTD.,
(CIN No. U40109 MH 2005 SFC 153646)

EHV CIVIL CONSTRUCTION CUM MAINTENANCE DIVISION-PARBHANI

EXECUTIVE ENGINEER (Civil)
MSETCL, EHV CCCM Division,
Old Power House Premises, Jintur Road, Parbhani (431 401).
Parbhani Dist :Parbhani -431 401

Tel (O) : **02452-242002** (O)
E-mail :
ee2720@mahatransco.in
Web: www.mahatransco.in

Work: The work of construction of retaining wall to tower (at Location Number 107) for 132kV Waghala -Jangamwadi line, Dist. Nanded.

Estimated Amount: -Rs. 2,85,168.00 /- (Inclusive of All Taxes)

Executive Engineer (C)
EHV CCCM Division,
MSETCL, Parbhani.

Quotation for Works

I/We hereby quote for the execution of the specified in the above written memorandum within time specified in such memorandum at (at Figure)% above/ below/ Estimated Rate (in Words) percent above/ Below/ Estimated rate (to be struck whichever is not applicable) the estimated rates (Incl. GST) entered in schedule “B” (memorandum showing item of work to be carried out) in accordance in all instruction in writing from the Engineer – in – Charge.

I/We have read the general conditions of contracts & the conditions enumerated in the quotation and the same are binding on us.

Signature of the contractor : _____

Name & Firm Seal : _____

Full Address : _____

EHV CIVIL CONSTRUCTION CUM MAINTENANCE DIVISION-PARBHANI

Work: The work of construction of retaining wall to tower (at Location Number 107)
for 132kv Waghala -Jangamwadi line, Dist. Nanded.

Abstract

S. N.	Description	Unit	Quantity	Rate (Inl. GST)	Amount
1	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.5 m.) By Mechanical Means	Cum	3.13	230.00	719.90
2	Excavation for foundation in hard murum including removing the excavated material up to distance of 50 metres beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift up to 1.50 m) By Mechanical Means	Cum	3.13	253.00	791.89
3	Providing and laying in situ cement concrete of 1:4:8 proportion with trap/granite/quartzite/gneiss metal in foundation including necessary form work, compacting and curing etc. complete.(with reversible drum type mixer with SCADA with fine aggregates of required specifications (Natural sand/VSI sand finely washed etc)	Cum	1.04	7,569.00	7,871.76
4	Providing and laying Cast in situ/Ready Mix cement concrete in M-20 of trap/ granite/ quartzite/ gneiss metal for R.C.C. pardi of required thickness including steel centering, formwork, cover blocks, laying/pumping, compacting , curing , finishing and roughening them if special finish is to be provided and curing complete. (Excluding reinforcement and structural steel).with reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)	Cum	9.92	18,129.0	1,79,839.68
5	Providing and fixing in position TMT - FE - 500 bar reinforcement of various diameters for R.C.C. pile caps, footings, foundations, slabs, beams columns, canopies, staircase, newels, chajjas, lintels pardis, copings, fins, arches etc. as per detailed designs, drawings and schedules. including cutting, bending, hooking the bars, binding with wires or tack welding and supporting as required complete.	MT	0.60	85,545.0	51,327.00

6	Providing internal cement plaster 20mm thick in single coat in cement mortar 1:4 without neeru finish to concrete or brick surfaces, in all positions including scaffolding and curing etc. complete	Sqm	41.76	456.00	19,042.56
7	Providing and applying two coats of exterior acrylic emulsion paint conforming to corresponding I.S. of approved manufacture and of approved colour to the plastered surfaces including cleaning, preparing the plaster surface, applying primer coat, scaffolding if necessary, and watering the surface for two days etc. complete	Sqm	41.76	286.00	11,943.36
8	Labour charges for skilled labour for tree cutting/minor work as directed by Engineer in charge.	Per day	4.00	690.00	2,760.00
9	Removing wire fencing with iron/C.C. fencing posts & stacking materials as directed with all leads, lifts etc. complete.	Rmt	25.00	75.00	1,875.00
10	Providing and laying weep holes of 100 mm diameter PVC pipes as per drawing for abutment returns, return walls etc. Complete.	Rmt	2.4	574.00	1,377.60
11	Dismantling the R.C.C. Work 1:2:4 and sorting out the materials such as steel etc. as directed and stacking them within the specified lead as directed etc. complete	Cum	4.68	1,628.00	7,619.04
	Total (Say) Rs. =				2,85,168.00


Executive Engineer (C)
EHV CCCM Division, MSETCL,
Parbhani