



MAHARASHTRA STATE ELECTRICITY TRANSMISSION COMPANY LTD.
[CIN No.U40109MH2005SGC153646]

From: - Executive Engineer[Civil]
EHV CCCM Division, 132KV OLD MIDC Jalgaon Sub-Station Premises, OLD MIDC Area, Ajintha road,
Jalgaon- 425 003. Phone :- 0257-2210094 , e-mail :- ee5720@mahatransco.in.

O. N.:- EEC/EHV/CCCM/Dn/JAL/Tech/ No 1 0 8 1

Date :- 25 JUL 2023

e-QUOTATION ENQUIRY

To,

.....
.....
.....
.....

Subject :- e-quotation enquiry for “Renovation of parking shed & septic tank at 132KV Amalner S/S Dist Jalgaon.”

Dear sir/madam,

Sealed percentage rate quotations are invited from Govt. registered & experienced contractors in similar works as per schedule enclosed. The quotation should reach to the office of Executive Engineer (Civil), EHV CCCM Division, Jalgaon on or before 01.08.2023 up-to 17:00 Hrs.

Sr No.	Name of Work	Estimated Cost (Inclusive of GST) EMD in Rs	Time limit of work	Last Date of Submission of Quotation	Probable date of opening (If possible)
1	“Renovation of parking shed & septic tank at 132KV Amalner S/S Dist Jalgaon.”	7,60,005.00 7,600.00	1 Month	01.08.2023 up to 17.00 Hrs.	02.08.2023 on 11.00 Hrs

Compulsory Primary Documents:

The contractor has to submit the self-attested copies of the documents listed below during the submission of offer.

- Valid Certificate of Registration of appropriate class for Civil works from PWD /MES/ Railways/ Jeevan Pradhikaran/CPWD ETC.OR from Any Govt. / Central Government.
- GST/ GSTIN Registration Certificate.
- Statement of Net worth for an amount equal to 25% of the estimated cost of work duly certified by Chartered Accountant. Net worth = Equity share Capital + Reserves – Revaluation reverse – Intangible assets - Miscellaneous expenditure to the extent not written off and carry forward losses.
- Average Financial Turn –over during the last 3 years ending 31st March of previous financial year should be at least 30% of the estimated cost. The agency has to submit annual Turnover Report / Profit and loss Accounts of last 3 years duly certified by Chartered Accountant / Registered Income Tax Practitioner.
- Agency has to submit the Certificate of Experience for execution of civil works in Govt. Organization as well as private sector duly signed by the officer not below

the rank of Executive Engineer or equivalent in case of Govt. works or from authorized authority of private sector, along with copies of agreement of work / work orders mentioned in the certificate for private sector work Experience of having successfully completed similar civil works during the last 7 years ending the last day of month previous to one in which the tenders are invited should be either of following.

a) "Three similar completed civil works costing not less than the amount equal to 40% of Estimated cost." OR

b) "Two similar completed civil works costing not less than the amount equal to 50% of Estimated cost." OR

c) "One similar completed civil works costing not less than the amount equal to 80% of estimated cost."

vi) E.P.F. Registration Certificate – issued by competent authority of Govt.

vii) The contractor has to pay earnest money in cash/in form of DD/FDR of any nationalized bank in favor of Executive Engineer (C), EHV CCCM Division, Jalgaon. If the EMD of required amount is not received in the envelope, the quotation will be rejected.


Viii) Bidders have to submit an undertaking in the attached Performa ANNEXURE-G declaring that their Firm is not Debarred/Blacklisted by Government/Semi Government/Other Power Utilities, anywhere. If it is revealed that the participating Bidder is Debarred/Blacklisted by Any Government/Semi-Government/Other Power Utility, anywhere, the Offer of such Bidder shall be liable for rejection at any stage of Quotation process. Further, if it is revealed that the successful Bidder is Debarred/Blacklisted by Any Government/ Semi-Government/ Other Power Utility, anywhere, then Order of such Bidder shall be liable for termination at any stage of Order execution process and the concern Bidder shall be solely responsible for the consequences arising there from.

Terms & conditions :

1. The work should be carried out as per PWD specifications & instructions of the Engineer in-charge & to the satisfaction of the undersigned.
2. The quantities mentioned in the attached schedule are approximate and likely to vary. However, payment will be made as per the work actually executed & measured. The rates shown in enclosed schedule-B are inclusive of GST.
3. The work which is of bad workmanship will not be measured & paid.
4. Other material such as required tools & plants are to be arranged by contractor at his own cost.
5. The contractor will have to make good the damages if any made by him during the execution of work at his own cost.
6. Income tax as per prevailing income tax rule & subsequent amendment thereof will be recovered at source of your bill on total value of work done for which the certificate will be issued if desired.
7. Contractor will be held responsible for accident occurred during the course of the work and will have to pay the compensation.
8. Contractor should submit his bill in triplicate through Addl Executive Engineer (C), EHV CCCM S/Dn Jalgaon-II. Payment will be made within 60 days period from the date of receipts of bill to this office.

9. The terms & conditions in the MSETCL booklet "Tender & Contract Work" will stand applicable for this work and final terms & conditions will be mentioned in work order.
10. The contractor's offer will be considered as inclusive of all taxes and charges and it will be the contractor's responsibility to pay the taxes to Government and same will not be reimbursed to the contractor.
11. Your own rates should be quoted in words and figures. Scratched & overwritten rates shall not be considered if not initialled.
12. The undersigned reserves the right to reject any or all quotations without assigning any reason whatsoever.
13. The payment shall be effected as per fund availability. Due to shortage of fund, there are chances of delay in payments for which the agency will have to bear with the department. Any of claim on this account will not be entertained.
14. Agency is instructed to subscribe on top of envelope *Quotation for the work of "Renovation of parking shed & septic tank at 132KV Amalner S/S Dist Jalgaon"* along with detail address, valid e-mail ID, contact number. Please note that the any correspondence in regard to the work if any will be done through e-mail only. Hence, agency's are requested to provide the valid e-mail currently in use for the communication and to check the e-mail ID regularly to get information of communication, if any. This office will not be responsible, if office unable to communicate to you due to invalid e-mail provided by you.

Encl- Schedule- B & Annexure-G


Executive Engineer (Civil)(I/C)
EHV Civil CCM Dn. Jalgaon

Copy SWRS to :

1. The Superintending Engineer (C), EHV CCCM Circle, nashik.

Copy to:-

1. Dy Manager (F&A), EHV CCCM Division, Jalgaon.




MAHARASHTRA STATE ELECTRICITY TRANSMISSION COMPANY LTD.
[CIN No.U40109MH2005SGC153646]

From: - Executive Engineer[Civil]
EHV CCCM Division, 132KV OLD MIDC Jalgaon Sub-Station Premises, OLD MIDC Area, Ajintha road,
Jalgaon- 425 003. Phone :- 0257-2210094 , e-mail :- ee5720@mahatransco.in.

Subject :- e-quotation enquiry for "Renovation of parking shed & septic tank at 132KV Amalner S/S Dist Jalgaon."

Estimated amount :- Rs. 7,60,005.00/- (Inclusive of all taxes)


Executive Engineer (Civil)(I/C)
EHV Civil CCM Dn. Jalgaon

Quotation for works

I/we hereby quote the execution of the specified in the above written memorandum within time specified in such memorandum at (at figure) _____ % above/below/estimated at par (in words) _____ percent above/below/estimated at par (To be cut/struck whichever is not applicable) the estimated rates entered in schedule-B (memorandum showing items of work to be carried out) in accordance with all instructions in writing from the Engineer-in-charge.

I/we have read the general conditions of contracts & the conditions enumerated in the quotation and the same are binding on us.

Signature of the contractor
with stamp :

Full address :

MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO.LTD.

EHV CCCM DIVISION, JALGAON

Subject :- e-quotation enquiry for “Renovation of parking shed & septic tank at 132KV Amalner S/S Dist Jalgaon.”

SCHEDULE-B


It. No.	Description of Item	Quantity	Rate including GST	Unit	Amount
1	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 metre beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting excetra complete. - (Lift upto 1.5 metre) By Mechanical Means	50.000	245.000	Cum	12250.000
2	Excavation for foundation in hard murum including removing the excavated material upto a distance of 50 metre beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting excetra complete. (Lift upto 1.5 metre) By Manual Means	15.000	433.000	Cum	6495.000
3	Providing and laying Cast in situ/Ready Mix, cement concrete in M-10 of trap/ granite/ quartzite/ gneiss metal for foundation and bedding including bailling out water, formwork, laying/ pumping, compacting and curing, excetra complete, with fully automatic micro processor based Programmable Logic Controller without Supervisory Control and Data Aquisition enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) excetra complete. With fine aggregate (Natural Sand / Crushed sand VSI Grade finely washed, excetra).	2.000	7657.000	Cum	15314.000
4	Providing dry trap/ granite/ quartzite/ gneiss rubble stone soiling 15 centimetre to 20 centimetre thick including hand packing and compacting, excetra complete.	26.000	2594.000	Cum	67444.000

5	<p>Providing and laying in situ/Ready Mix cement concrete M-20 of trap/ granite/ quartzite/ gneiss metal for reinforced cement concrete work in foundations like raft, strip foundations, grillage and footings of reinforced cement concrete columns and steel stanchions, excetra including bailling out water, formwork, cover blocks, compaction, curing and roughening the surface if special finish is to be provided (Excluding reinforcement and structural steel), excetra complete, with fully automatic micro processor based Programmable Logic Controller without Supervisory Control and Data Aquisition enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) excetra complete. With fine aggregate (Natural Sand / Crushed sand VSI Grade finely washed etc)</p>	4.000	9082.000	Cum	36328.000
6	<p>Providing and laying cast in situ / Ready Mix cement concrete M-20 of trap / granite /quartzite/ gneiss metal for reinforced cement concrete columns as per detailed designs and drawing or as directed, including steel centering, formwork, cover blocks,aying/pumping, compaction, finishing the formed surfaces with cement mortar 1:3 of sufficient minimum thickness to give a smooth and even surface or roughening the surface if special finish is to be provided and curing, excetra complete. (Excluding reinforcement and structural steel). with fully automatic micro processor based Programmable Logic Controller without Supervisory Control and Data Aquisition enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) excetra complete.with fine aggregate (Natural Sand / Crushed sand VSI Grade finely washed etc) (For Ground Floor)</p>	4.000	17003.000	Cum	68012.000
7	<p>Providing and fixing in position thermo mechanically treated FE-500 steel bar reinforcement of various dias for reinforced cement concrete pile caps, footings, foundations, slabs, beams, columns, canopies, staircases, newels, chajjas, lintels, pardis, copings, fins, arches, excetra as per detailed designs, drawings and schedules including cutting, bendding, hooking the bars, binding with wires or tack welding and supporting as requied complete. (For Ground Floor)</p>	1.000	106379.000	MT	106379.000

8	<p>Providing and fabricating structural steel work in rolled sections like joists, channels, angles, tees, excetra as per detailed designs and drawing or as directed including cutting, fabricating, hoisting, erecting, fixing in position making riveted / bolted / welded connections without connecting plates, braces, excetra and including one coat of anticorrosive paint and over it two coats of oil painting of approved quality and shade, excetra complete. (For Ground Floor)</p>	1.000	120777.000	MT	120777.000
9	<p>Providing and fixing of colour coated zincalume (R) AZ 150 (Minimum 150 grams per square metre total on each sides) profiled sheets for roofing. The feed material is manufactured out of nominal 0.45 milimetre base metal thickness (BMT) (0.5 milimetre TCT), Hi-strength steel with minium 550 MPa yield strength, metallic hot dip coated with Aluminium-Zinc alloy (55 percent aluminium, 43.4 percent zinc, 1.6 percent silicon) with COLORBOND (R) steel quality super durable polyester paint coat (with inorganic pigment). The paint shall have a total coating thickness of nominal 35 um, comprising of nominal 25 um exterior coat on top surface and nominal 10 um reverse coat on back surface. Profile sheet shall have nominal 950-1050 milimetre effective cover width and nominal 25-30 milimetre deep ribs with subtle square fluting in the five pan at nominal 180-250 milimetre center to centre. The end rib shall be designed for anti capillary groove and return leg. The feed material should have coil manufacturer's product details marked at regular interval. Including fasteners with minium fatened with minium 25 um zinc-tin alloy coated, hex head, self-drilling screw, excetra complete. (Weight of profile 4.52 kilogram per square metre). (For Ground Floor)</p>	69.000	1391.000	Sq mt	95979.000
10	<p>Providing and fixing polyvinyl chloride coloured ridge tiles over unplasticised polyvinyl chloride roofing where required having size 113 centimetre X 41 centimetre and height 9.5 centimetre for ridge including fastening with self drilling screw having washers made of stainless steel, excetra complete. (For Ground Floor)</p>	14.000	1642.000	Rmt	22988.000

11	Providing and fixing heavy duty inter locking concrete coloured paving blocks of 60 milimetre thickness of having a strength of 300 kilogramme per square centimetre of approved quality and shape on a bed of crushed sand of 25 milimetre to 30 milimetre thick including striking joints and cleaning, excetra complete.	78.000	1101.000	Sq mt	85878.000
12	Supplying soft murum at the road site, including conveying and stacking, excetra complete.	6.000	1191.000	Cum	7146.000
13	Labour charges for Mazdoor unskilled light Male at the site of work.	5.000	729.000	Nos	3645.000
14	Providing internal cement plaster 12 milimetre thick in a single coat in cement mortar 1:4 without neeru finish to concrete or brick surfaces, in all positions including scaffolding and curing, excetra complete. (For Ground Floor)	5.000	345.000	Sq mt	1725.000
15	Providing and applying two coats of textured synthetic paint of approved shade and quality and one coat of primer before applying textured paint including scaffolding if necessary, preparing the surface by thoroughly cleaning oil, grease, dirt and other materials as required, excetra complete. (For Ground Floor)	5.000	193.000	Sq mt	965.000
16	Providing and laying in situ cement concrete M-30 with tremix treatment for 200 milimetre thickness for concrete road including laying plastic sheet of 125 micron thickness with groove cutting of 4 milimetre wide and 20 milimetre deep with necessary refilling with bitumen (excluding reinforcement) with coarse and fine aggregate (V.S.I. grade finely washed crushed sand) excetra complete.	1.000	10429.000	Cum	10429.000
17	Providing and laying cast in situ / Ready Mix Cement concrete M-20 of trap/ granite/ quartzite/ gneiss metal for reinforced cement concrete pardi of required thickness including centering, formwork, cover blocks, compacting, finishing and roughening them if special finish is to be provided and curing complete. (Excluding reinforcement, including cover block) Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin excetra with fully automatic micro processor based Programmable Logic Controller without Supervisory Control and Data Aquisition enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) excetra complete. With fine aggregate (Natural Sand / Crushed sand VSI Grade finely washed etc)	1.000	19118.000	Cum	19118.000

18	Providing and laying cast in situ / Ready Mix cement concrete M-20 of trap/ granite / quartzite/ gneiss metal for reinforced cement concrete slabs and landings as per detailed designs and drawings including steel centering, formwork, cover blocks, laying / pumping, compaction, finishing the formed surfaces with cement mortar 1:3 of sufficient minimum thickness to give a smooth and even surface or roughening the surface if special finish is to be provided and curing, excetra complete. (Excluding reinforcement and structural steel). with fully automatic micro processor based Programmable Logic Controller without Supervisory Control and Data Aquisition enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) excetra complete. With fine aggregate (Natural Sand / Crushed sand VSI Grade finely washed etc)	1.000	17179.000	Cum	17179.000
19	Providing, laying and fixing, jointing Eco-drain 160 milimetre SN 4 Nu-Drain unplasticized poly vinyl chloride pipes or of equivalent make, manufacture as per EN 13476 or equivalent as per Indian Standard : 15328 with fittings such a bends, tees, coupler, excetra jointing with rubber lubricant including necessary excavation, trench refilling with selective excavated material, excetra complete.	20.000	602.000	Rmt	12040.000
20	Providing and constructing brick masonry inspection chamber 60 centimetre X 45 centimetre X 90 centimetre including 1:4:8 cement concrete foundation, 1:2:4 cement concrete channels, half round glazed stoneware pipes, brick masonry, plastering from inside and airtight cast iron lid 75 kilogram with frame fixed in cement concrete, excetra complete.	3.000	16638.000	Nos	49914.000
Total amount including 18% GST					760005.00


Executive Engineer (Civil)(I/C)
EHV Civil CCM Dn. Jalgaon

ANNEXURE 'G'

Undertaking to be submitted by the Bidder declaring that Bidder is not Debarred/Blacklisted by Government/Semi-Government/Other Power Utilities.

I/We hereby declare that I/We is/are participating in MSETCL's e-quotation enquiry for the work of "Renovation of parking shed & septic tank at 132KV Amalner S/S Dist Jalgaon" as on date of submission of this quotation, I/We hereby declare that My Firm/We is/are not Debarred/Blacklisted by Any Government/ Semi-Government/Other Power Utilities, anywhere.

The above declaration is true to the best of My/Our knowledge and belief.

I/We hereby agree that in case My Firm/We are Debarred/Blacklisted by Any Government/ Semi-government/Other Power Utilities, anywhere, My/Our Offer is liable for rejection at any stage of Tendering process as per Tender Conditions. Further, I/We hereby understand and agree that in case My Firm/We are Debarred/Blacklisted by Any Government/ Semi-Government/Other Power Utilities, anywhere, My/Our Order is liable for termination at any stage of Order execution process and My Firm/We shall be solely responsible for the consequences arising out of it.

Authorized Signatory, Stamp/Seal of the firm