

**MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD**  
(CIN No. U40109MH2005SGC153646)

<b>From</b> The Chief Engineer (C&M), 5 <sup>th</sup> Floor, A-Wing, Prakashganga, C-19, "E" Block, Bandra – Kurla Complex, Bandra (East), Mumbai – 400 051. Tel: 022-2659 5125 (O)/022-2659 5124 (P) E-mail: cecm@mahatransco.in	<b>To</b> M/s Sharvari Electricals Office No. 501 To 504, 5th Floor, Sai Business Centre, Near Utsav Mangal Karyalay Osmanpura, Aurangabad – 431 005 Tel: 0240 – 2322656, 2344375, 7875022656 E-mail: sharvari.electricals@gmail.com
---	--

MSETCL/CO/C&M/Pre-T/SSPre-Tender/

**05459**

Date:

**24 JUL 2019**

**Sub:** Letter of Award for “Establishment of 132/33 kV substation at Kothali (Excluding Civil portion) Dist. Jalgaon under Nashik Zone on turnkey basis against tender no. T-1873 (RFx No. 6000000660)”.

- Ref:**
- 1) SRM e -Tender No. T-1873/MSETCL/CO/C&M/Pre-T/Pre-Tender (RFx No. 6000000660)
  - 2) Your offer dtd. 23.11.2018 against subject tender.
  - 3) Scheme B.R. No. 122/09 dtd. 30.10.2017
  - 4) Tender acceptance B.R. No. 135/20 dtd. 06.06.2019
  - 5) MERC approval –MERC/Capex/MSETCL/2017-18/0307 dtd. 05.03.2018

Dear Sir,

In connection with above subject, we are pleased to inform you that your above referred offer for the work of establishment of 132/33 kV substation at Kothali (Excluding Civil portion) Dist. Jalgaon on turnkey basis under Nashik Zone has been accepted. The details are as follows.

**Part A- Supply of materials**

<b>Description of works</b>	<b>Final Price quoted in Rs.</b>
Supply of equipments and materials for the work of establishment of 132/33 kV substation at Kothali (Excluding Civil portion) Dist. Jalgaon on turnkey basis under Nashik Zone for following scope of work:- 1) 25 MVA 132/33 kV Transformer with bays- 02 nos. 2) 132 kV line bay - 02 nos. 3) 33 kV outlet - 06 nos.	<b>Rs. 10,23,67,451.08</b> (Including all Taxes & Duties)

(Rs. Ten Crore Twenty-three Lakh Sixty-seven Thousand Four Hundred Fifty-one and Eight Paise Only.)

The activity schedule for supply work is enclosed herewith.

It may please be noted that the scope shall also include supply of all equipments/materials which are not specifically listed in your offer but are necessary in order to meet the requirements of the substation  
Sub: Letter of Award for “Establishment of 132/33 kV substation at Kothali (Excluding Civil portion) Dist. Jalgaon under Nashik Zone on turnkey basis against tender no. T-1873 (RFx No. 6000000660)”.

as per tender specifications in all respect. Detailed terms and conditions will be as per the tender specifications, amendments thereof, your offer, clarifications thereon and contract agreement being executed shortly. The balance excess/extra material will not be accepted by MSETCL. Therefore the agency should take care for appropriate supply of material to complete the turnkey project. The work of above substation has to be completed within 12 months from the date of handing over of site (including monsoon).

**Part B – ETC of materials**

Description of works	Final Price quoted in Rs.
Erection, Testing & Commissioning of equipments and materials for the work of establishment of 132/33 kV substation at Kothali (Excluding Civil portion) Dist. Jalgaon on turnkey basis under Nashik Zone for following scope of work:- 1) 25 MVA 132/33 kV Transformer with bays- 02 nos. 2) 132 kV line bay - 02 nos. 3) 33 kV outlet - 06 nos.	<b>Rs. 44,26,307.73</b> (Including all Taxes & Duties)

(Rs. Forty-four Lakh Twenty-six Thousand Three Hundred Seven and Seventy-three Paise only.)

The activity schedule for erection work is enclosed herewith.


It may please be noted that the scope shall also include erection, testing and commissioning of all equipments/materials which are not specifically listed in your offer but are necessary in order to meet the requirements of the substation as per tender specifications in all respect. Detailed terms and conditions will be as per the tender specifications, amendments thereof, your offer, clarifications thereon and contract agreement being executed shortly. The work of above substation has to be completed within 12 months from the date of handing over of site (including monsoon)

You are requested:-

1. To intimate the acceptance of this LoA within 10 days from receipt of LoA.
2. To submit the bar chart indicating all activities for completion of the S/S within 10 days.
3. To submit price schedule with detailed break up of unit rate into ex-works price, tax, freight & insurance etc. within 10 days from receipt of LoA.
4. To complete the formalities like furnishing of Performance Bank guarantee as per the Clause No. 6.0 of Section-II of Book-I in prescribed format so that the contract agreement can be finalized.

Thanking you.

Encl: Activity schedules.

Yours faithfully,  
  
 Chief Engineer (C&M)

Copy s.w.rs. to:

- 1) The Director (Projects), MSETCL, Mumbai.

Copy f.w.cs. to:

- 1) The C.E., EHV PC O&M Zone, MSETCL, Nashik.
- 2) The C.E., Project Scheme/Civil/D&P, MSETCL, Mumbai.
- 3) The C.G.M. (F&A), MSETCL, Mumbai.

Copy to:

- 1) The G.M. (F&A, Projects), MSETCL, Mumbai.
- 2) The S.E., EHV Projects Circle, MSETCL, Nashik.
- 3) The S.E., EHV Civil CCM Circle, MSETCL, Nashik.
- 4) The S.E. (Post Tender), C.O. MSETCL, Mumbai.
- 5) The E.E., EHV Projects Division, Jalgaon.
- 6) The E.E., EHV Civil CCM Division, Jalgaon
- 7) The E.E. (D&E-S1)/(D&E-S-2), C.O. MSETCL, Mumbai.
- 8) The E.E., PMT, MSETCL, Mumbai. ....For further needful
- 9) The E.E., FTU, MSETCL, Mumbai. ....For further needful



### Activity Schedule for Supply of Material

Tender No.: T-1873/MSETCL/CO/C&M/Pre-T/SSPre-Tender (RFx No. 6000000660)

Name of Work: Establishment of 132/33 kV Substation at Kothali (excluding Civil portion), Dist. Jalgaon, Maharashtra.

Name of Contractor: M/s Sharvari Electricals, Aurangabad

Completion Period: 12 months from the date of handing over of site.

Sr. No.	Name of the material	Scheduled period for supply of material from the date of handing over of site	Hold point for payment
1	Soil investigation, Drawing submission i.e. layout, Erection Key Diagram, Gantry Structure, Equipment Structure, Earth mat Design, Cable Trench, Control Room & Foundation Drawing etc.	Submission within 30 days	
2	Gantry Materials	Commencement after 30 days & completion within 120 days.	Gantry material should be as per approved layout & site requirement and equivalent to gantry foundations casted.
3	Equipment Structures	Commencement after 30 days & completion within 120 days.	Equipment structures should be as per requirement worked out from approved layout and equivalent to respective equipment foundations casted.
4	Conductor, Insulators Hardwares etc.	Commencement after 75 days & completion within 180 days.	Completion of 100% gantry foundations & 50% gantry erection.
5	CTs, PTs, LA, Isolator, BPI, CC, WT, Clamp & Connectors, M.K.	Commencement after 90 days & completion within 240 days.	1. Completion of erection of 100% gantries with bus bar stringing. 2. Erection of respective equipment structure.
6	MS Flats, CI Pipes, Earthing Material, Yard Lighting, ACDB, Power & Control Cables, Cable Trays	Commencement after 120 days & completion within 180 days.	Material should be as per finalization of BoQ by Engineer in charge as per actual requirement based on approved drawing and erection of 100% gantries with bus bar stringing.
7	Circuit Breakers, Capacitor Banks, Power Transformers & Station Transformer	Commencement after 230 days & completion within 270 days	1. Completion of all equipment foundations & erection of it, 100% gantries with bus bar stringing and transformer plinth, completion of 100% cable trench with laying of cable trays. 2. Completion of unfinished main

			control room * and 100% BCR.
8	PLCC Equipments, HF Cable, PLCC Panels / DCDB, FOTE Panel etc.	Commencement after 200 days & completion within 230 days.	Completion of all bay equipments except circuit breaker, power transformer / ICT and complete finishing of PLCC room.
9	Control & Relay Panels, SCADA, ABT Meter, Battery Sets, Battery Chargers & Fire Fighting Equipments.	Commencement after 240 days & completion within 285 days.	Completion of control room, bay control rooms & erection of respective bay equipments & laying of respective control cable.
<p><b>Note:</b></p> <ol style="list-style-type: none"> <li>1. The contractor may supply the material prior to schedule delivery period. However, the payment eligibility will be as per hold points indicated above.</li> <li>2. *Unfinished control room: Completion of slab, brick work &amp; plastering.</li> <li>3. Please ignore the activities/hold points which are not covered in scope of this tender.</li> </ol>			

### Activity Schedule for Erection Work

Tender No.: T-1873/MSETCL/CO/C&M/Pre-T/SSPre-Tender (RFx No. 6000000660)

Name of Work: Establishment of 132/33 kV Substation at Kothali (excluding Civil portion), Dist. Jalgaon, Maharashtra.

Name of Contractor: M/s Sharvari Electricals, Aurangabad

Completion Period: 12 months from the date of handing over of site.

Sr. No.	Activity	No. of days/months from the date of handing over of site		Hold point for payments	Remarks
		Commencement	Completion		
	<b>ERECTION</b>				
1	Mobilization of gang	Within 30 days			
2	Arrangement of work and power supply, tests etc.	Within 30 days			
3	Erection of gantry structures and stringing of bus bar	Within 75 days	Within 180 days.		
4	Equipment structures	Within 75 days	Within 135 days.		
5	CT, PT, LA, Isolator, & BPI	Within 120 days	Within 270 days.		
6	Earthing, layout of earth mat, cable laying, cable trenches & yard lighting	Within 150 days	Within 210 days.		
7	PLCC equipments i.e. WT CC, DCDB, & PLC terminal	Within 210 days	Within 300 days.		
8	Erection of Circuit Breakers, Capacitor banks, power transformer and stations transformer	Within 240 days	Within 300 days		
9	Installation of C&R panels, ABT Meter, battery & battery charger.	Within 230 days	Within 310 days.		
10	Pre commissioning trials / testing.	Within 240 days	Within 330 days.		
11	Electrical installation.	Within 210 days	Within 340 days.		

Note: Please ignore the activity if not covered in scope of tender.